T-box Zone

Modbus RTU communication with SYSTEM Flowair via T-box ZONE

3

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

2

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

3

1. Modbus Documentation

1.1. Protocol parameters

1	Standard	RS485
2	Baudrate	9600, 19200, 38400, 57600, 76800, 115200, 230400
3	Data bits	8
4	Parity	Even; None; Odd
5	Stop bits	1; 2
6	Version	Modbus RTU
7	Addressing convention	Register address starting from 0
8	Data type	Unsigned Int16 (if not stated otherwise)

1.2. MODBUS functions

Read Holding Register	0x03
Read Input Register	0x04
Write Single Register	0x06
Write Multiple Registers	0x10

1.3. T-box ZONE settings:

Flowair System can be controlled via Building Management System (refereed to as BMS) **using T-Box Zone as a gate to access all available Flowair devices.** T-box settings are unblocked. All the settings can be changed via MODBUS RTU.

Direct access to single DRV or group of DRV's settings depends on Zone configuration, see example bellow:

Zone 1 (set in T-box): DRV ELIS dip switch addresses 1; DRV ELIS dip switch addresses 2 set in the same Zone.

- In this case group from two DRV ELIS is created. Controlling (Holding Register) of two units at the same time (Input Register available for each DRV ELiS)

For direct access to control each DRV ELIS please set it in separate zones.

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

4

1.4. How to Control DRV's in MODBUS :

1. Map of connecting DRV's with information about addresses and Zones in chapter 1.5. (Input Register 0x10)
2. There is two options Control DRV's (Holding Register):

    a) using dynamic info two parameters should be set:
        I.   Zone ID on 0x2300
        II.   Device ID on 0x2301 (device ID is unique value for Each type of DRV)
        Than:
        III. Register 0x2302 will be 0x00 from DRV Holding Registers (example: DRV ELIS; 0x00 Work Mode)
        IV.   Register 0x2303 will be 0x01 from DRV Holding Registers (example: DRV ELIS; 0x01 CurtainFanSpeedRef)
        V.   Etc.

    b) using static space .
        I.   Register 0x2320 will be 0x00 from DRV Holding Registers (example: DRV ELIS; 0x00 Work Mode)
        II.   Register 0x2321 will be 0x01 from DRV Holding Registers (example: DRV ELIS; 0x01 CurtainFanSpeedRef)
        III. Next Group/DRV address is starting from 0x2340. Length 32 for each Holding registers space.

3. To Read information from each DRV. (Input Register):
    I.   Register 0x0140 from DRV Input Register (example: DRV ELIS; 0x01 Software Type)
    II.   Register 0x0143 from DRV Input Register (example: DRV ELIS; 0x04 Temperature measured by T3 sensor)
    III. Next DRV address is starting from 0x160. Length 32 for each Input registers space

1.5. Masked Registers

Masked registers were introduced to pack indepedend information to one 16-bit register. To extract information user has to apply correct mask by using **and** logic operator ($\wedge$) and **shift** operator ($\Rightarrow$).

1.5.1. Masked Register Example

Fuse state for EC/3V/Roof fans, information can be read from 4 bits.

Parameter name	Description	Shift	Mask	Value
FAN_ROOF	Fan roof fuse state	0	15	fuse_condition
FAN_EC	Fan EC fuse state	4	240	fuse_condition
FAN_3V	Fan 3V fuse state	8	3840	fuse_condition

Note

Table shows indepedend information that can be extraced from this register. Value column points to expected return values and their interpretation.

fuse_condition

Parameter name	Description	Value
NOT_SET	Not set.	0
FUSE_OK	Fan fuse is OK	1
FUSE_BLOWN	Fan fuse is BLOWN.	2

Note

Table shows how to interpret information after applying mask and shift.

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

5

1.5.2. How to extract values

assumption

Device returned value **4384** from masked register example.

task

Extract **FAN_EC** fuse condition.

Math representation

$$\text{Value} \wedge \text{mask} \Rightarrow \text{shift} = \text{result}$$

$$4384 \wedge 240 \Rightarrow 4 = 2$$

Python implementation

```python
1  def extract_masked_value(value, mask, shift):
2      return (value & mask) >> shift
```

C implementation

```c
1  uint16_t extract_masked_value(uint16_t value, uint16_t mask, uint16_t shift) {
2      return ((value & mask) >> shift);
3  };
```

Lastly interpret recived value according to **fuse_condition** table.

FUSE_BLOWN	Fan fuse is BLOWN.	**2**

Tip

Depending on how the information is split through the register it might be easier to read in a hexadecimal format. From our example **4384** can be represented as hex **0x1120** (0 - NOT_SET, 1 - FUSE_OK etc.). Presenting value in hex format helps when information is written on nibbles, binary format is more suitable for information written on bits.

1.5.3. Alarms

There are few types of ALARMs all register of them are mark by ALARM word.

e.g.

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

6

Parameter name	Description	
0x7FFF	PT1000 sensor not connected	**ALARM**
0x02	Water Exchanger	**ALARM**
	Antifreeze enabled (user parameters overwritten)	
0x02	Fan fuse is BLOWN.	**ALARM**
0x7FFF	PT1000 sensor not connected	

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

7

1.6. T-Box Zone general parameters (Controler)

1.6.1. Holding Register

Address	Name	Description		
0x00	SetScreenLock	Turn on screen lock.		
		Parameter name	**Description**	**Value**
		OFF_0	Disabled.	0
		ON_1	Enabled.	1
0x01	EnableDisableController	Enables or disables controller and all connected devices.		
		Parameter name	**Description**	**Value**
		OFF_0	Disabled.	0
		ON_1	Enabled.	1
0x02	UnlockScreen	Unlocks screen. Viable while screen lock is turned on.		
		Parameter name	**Description**	**Value**
		OFF_0	Disabled.	0
		ON_1	Enabled.	1
0x03	Null_7	Register not used.		
		Parameter name	**Description**	**Min** / **Max**
		Unit16_range	Register not used.	0 / 65535
0x04	SetYear	Datetime setting. Set year.r.		
		Parameter name	**Description**	**Min** / **Max**
		YEAR	Set year.	2021 / 2035
0x05	SetMonth	Datetime setting. Set month.		
		Parameter name	**Description**	**Min** / **Max**
		MONTH	Set month.	0 / 11
0x06	SetDay	Datetime setting. Set day.		
		Parameter name	**Description**	**Min** / **Max**
		RANGE_1_31	Range 1-31	1 / 31
0x07	SetHours	Datetime setting. Set hour.		
		Parameter name	**Description**	**Min** / **Max**
		HOUR	Set day	0 / 23
0x08	SetMinutes	Datetime setting. Set Minute.		
		Parameter name	**Description**	**Min** / **Max**
		SEXAGESIMAL	Set minutes or seconds.	0 / 59
0x09	SetSeconds	Datetime setting. Set second.		
		Parameter name	**Description**	**Min** / **Max**
		SEXAGESIMAL	Set minutes or seconds.	0 / 59
0x0A	SetExternalSignalEnable	External signal Handling		

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📞 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

8

Address	Name	Description		
		Parameter name	**Description**	**Value**
		OFF_0	Disabled.	0
		ON_1	Enabled.	1
0x0B	SetExternalSignalMode	External signal mode/functionality		
		Parameter name	**Description**	**Value**
		OFF_0	Disabled.	0
		ON_1	Enabled.	1
0x0C	SetExternalSignalContact	External signal contact configuration		
		Parameter name	**Description**	**Value**
		NO_0	Normally open.	0
		NC_1	Normally close.	1
0x0D	SetExternalSignalLevel	External signal level		
		Parameter name	**Description**	**Value**
		GLOBAL_0	Global all drvs.	0
		ZONES_1	Zones select.	1

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia NIP: 9581440661 58 627 57 20 info@flowair.pl **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

9

1.6.2. Input Register

Address	Name	Description
0x00	hardware_type	Information about hardware type and it's version.

Parameter name	Description	Shift	Mask	Value
PCB_VERSION	<LSB>PCB version	0	255	pcb_v
PCB_name	<MSB>PCB name	0	65280	pcb_n

pcb_v

Parameter name	Description	Value
PCB-VERSION_CONT	<LSB>PCB Version	

pcb_n

Parameter name	Description	Value
NOT_SET	Not set.	0
DRV_OXEN	OXEN Driver	256
DRV_ELIS	ELIS Driver	512
DRV_KM	KM Driver	768
DRV_M	M Driver	1024
DRV_V	V Driver	1280
PSENS_HARDWARE	Sensor device	1536
CUBE	Rooftop driver	1792
DRV_ELIS_EC	DRV ELIS EC	2048
LUNA	LUNA	2306

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

10

Address	Name	Description
0x01	Software_type	Information about hardware type and it's verson.

Parameter name	Description	Value
OXEN	OXEN	257
CURTAIN	CURTAIN	513
KM	KM	769
HEATER_EC	HEATER_EC	1025
DESTRATIFICATOR_AC	DESTRATIFICATOR	1281
DESTRATIFICATOR_EC	DESTRATIFICATOR_EC	1283
CURTAIN_HEATER	CURTAIN_HEATER	1537
HEATER_AC	HEATER_AC	1793
HEATER_AC_EL	HEATER_AC_EL	1794
KM_RAW	KM_RAW	2305
ROBUR_PN	ROBUR_PN	2561
COOL	COOL	2817
ROBUR_KM	ROBUR_KM	4097
ROBUR_KM_NEXT	ROBUR_KM_NEXT	4098
ROBUR	ROBUR	4353
ROBUR_NEXT	ROBUR_NEXT	4354
DRV_V_RAW	DRV_V_RAW	4865
PSENS_ABS	PSENS ABSOLUTE	5121
PSENS_DIFF	PSENS DIFFERENTIAL	5122
PSENS_DIF_60	PSENS DIFFERENTIAL 60mBar	5123
CUBE	CUBE	5377
LUNA	LUNA	5890
ELIS AX	ELIS AX	6146

Address	Name	Description
0X02	connection_count	Connection count. Increased each time register is read. First query always returns value 0x01. If register value equals 0zFFFF before the query, next one will be equal to 0x00. Monitoring this register enables system diagnostics (e.g. if the program was not deployed second time after voltage shortage).

Parameter name	Description	Min	Max
CONNECTION_COUNT	Connection Count	0	65535

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

11

Address	Name	Description
0x03	soft_ver	Software version.

Check out ourguide on how to extract information from masked register

Parameter name	Description	Shift	Mask	Value
TAG	TAG	0	15	major_minor
MINOR	MINOR	4	240	major_minor
MAJOR	MAJOR	8	3840	major_minor

major_minor

Parameter name	Description	Value
MAJOR_MINOR	MAJOR MINOR	

Address	Name	Description
0x04	main_sensor_reading	Temperature measured by main sensor.

Parameter name	Description	Min	Max	Value	Step	Multiplier
TEMPERATURE	Temperature.	-1500	2000		5	0.1
SHORT_CIRCUIT	Short circuit.			28672		
PT1000_NC	Sensor not connected.			32767		

Address	Name	Description
0x05	secondary sensor reading	Temperature measured by secondary sensor.

Parameter name	Description	Min	Max	Value	Step	Multiplier
TEMPERATURE	Temperature.	-1500	2000		5	0.1
SHORT_CIRCUIT	Short circuit.			28672		
PT1000_NC	Sensor not connected.			32767		

Address	Name	Description
0x06	NULL_6	Register not used.

Parameter name	Description	Min	Max
Unit16_range	Register not used.	0	65535

Address	Name	Description
0x07	NULL_7	Register not used.

Parameter name	Description	Min	Max
Unit16_range	Register not used.	0	65535

Address	Name	Description
0x08	Device Count	Discovered devices count.

Parameter name	Description	Min	Max
RANGE_0_31	Count in range 0-31.	0	31

Address	Name	Description
0x09	Zone Count	Zone count.

Parameter name	Description	Min	Max
RANGE_0_31	Count in range 0-31.	0	31

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

12

Address	Name	Description			
0x0A	GroupCount	Group count.			

Parameter name	Description	Min	Max
RANGE_0_31	Count in range 0-31.	0	31

Address	Name	Description
0x0B	DeviceStatus_1_16	Discovered devices status.

Parameter name	Description	Shift	Mask	Value
DRV_01	Device 01 status	0	1	device_status
DRV_02	Device 01 status	1	2	device_ststus
DRV_03	Device 03 status	2	4	device_ststus
DRV_04	Device 04 status	3	8	device_status
DRV_05	Device 05 status	4	16	device_status
DRV_06	Device 06 status	5	32	device_status
DRV_07	Device 07 status	6	64	device_status
DRV_08	Device 08 status	7	128	device_status
DRV_09	Device 09 status	8	256	device_status
DRV_10	Device 10 status	9	512	device_status
DRV_11	Device 11 status	10	1024	device_status
DRV_12	Device 12 status	11	2048	device_status
DRV_13	Device 13 status	12	4096	device_status
DRV_14	Device 14 status	13	8192	device_status
DRV_15	Device 15 status	14	16384	device_status
DRV_16	Device 16 status	15	32768	device_status

device_status

Parameter name	Description	Value
ERROR_0	Error	0
OK_1	Ok	1

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

13

Address	Name	Description
0x0C	DeviceStatus _17_32	Discovered devices status.

Parameter name	Description	Shift	Mask	Value
DRV_17	Device 17 status	0	1	device_status
DRV_18	Device 18 status	1	2	device_status
DRV_19	Device 19 status	2	4	device_status
DRV_20	Device 20 status	3	8	device_status
DRV_21	Device 21 status	4	16	device_status
DRV_22	Device 22 status	5	32	device_status
DRV_23	Device 23 status	6	64	device_status
DRV_24	Device 24 status	7	128	device_status
DRV_25	Device 25 status	8	256	device_status
DRV_26	Device 26 status	9	512	device_status
DRV_27	Device 27 status	10	1024	device_status
DRV_28	Device 28 status	11	2048	device_status
DRV_29	Device 29 status	12	4096	device_status
DRV_30	Device 30 status	13	8192	device_status
DRV_31	Device 31 status	14	16384	device_ststus
TBOX	TBOX status	15	32768	device_status

device_status

Parameter name	Description	Value
ERROR_0	Error	0
OK_1	Ok	1

Address	Name	Description
0x0D	ControlerStatus_1_16	Discovered controler status – 32 bit value.

Parameter name	Description	Min	Max
INFO_MAP_Range	Shift.	0	65535

Address	Name	Description
0x0E	ControlerStatus_17_31	Discovered controler status - 23 bit value.

Parameter name	Description	Min	Max
INFO_MAP_RANGE	Shift.	0	65535

Address	Name	Description
0x0F	InfoStartpoint	Dynamic device info startpoint.

Parameter name	Description	Value
STARTPOINT	Startpoint.	12345

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   www.flowair.com

T-BOX Zone Modbus RTU V4.7.docx

14

1.6.3. Input Register (DRV's mapping)

1.6.3.1. Cluster

This section is a `cluster` – content is repeated to reduce clutter. Each `controller` can handle up 31 `devices` so this section is
repeated: 31
lenght: 8

Address	Name	Description			
0x10	DeviceID	Modbus ID (address set on dipswitch)			
		Parameter name	**Description**	**Min**	**Max**
		RANGE_1_31	Range 1-31	1	31
0x11	DeviceStatus01	Device Status 01. Any value other than **0** indicates an **ALARM**			
0x12	DeviceStatus02	Device Status 02 Any value other than **0** indicates an **ALARM**			
0x13	ZoneID	Zone ID (Zone number)			
		Parameter name	**Description**	**Min**	**Max**
		RANGE_1_31	Range 1-31	1	31
0x14	DeviceGroupID	Device group ID			
		Parameter name	**Description**	**Min**	**Max**
		INFO_MAP_RANGE	Shift	0	65535
0x15	DeviceReadingsStartPoint	Device readings start point (starting point for INPUT REGISTERS for specific unit)			
		Parameter name	**Description**	**Min**	**Max**
		INFO_MAP_RANGE	Shift	0	65535
0x16	ZoneReadingsStartPoint	Device zone readings start point.			
		Parameter name	**Description**	**Min**	**Max**
		INFO_MAP_RANGE	Shift	0	65535
0x17	NULL_6	Register not used.			
		Parameter name	**Description**	**Min**	**Max**
		Unit16_range	Register not used.	0	65535

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

15

1.7. Zone Registers T-box ZONE

1.7.1. Holding Register - Dynamic Info (T box Zone settings)

Address	Name	Description					
0x900	SetZoneID	Set Zone ID that indicates what zone is being changed.					
		Parameter name	**Description**	**Min**		**Max**	
		RANGE_1_31	Set Zone ID	1		31	
0x901	EnableDisableZone	Enables or disables all zone devices.					
		Parameter name	**Description**	**Value**			
		OFF_0	Disabled	0			
		ON_1	Enabled	1			
0x902	ZoneTRef	Target temperature.					
		Parameter name	**Description**	**Min**	**Max**	**Step**	**Multiplier**
		TEMP_REF	Target temperature	50	450	5	0.1
0x903	ZoneAntifreeze	Enable zone antifreeze.					
		Parameter name	**Description**	**Value**			
		ON_1	Enabled	1			
		OFF_2	Disabled	2			
0x904	ZoneTLeadSensorSelect	Target temperature to enable zone antifreeze.					
		Parameter name	**Description**	**Min**	**Max**	**Step**	**Multiplier**
		AF_WH_TEMP_REF	Target temperature	50	150	5	0.1
0x905	ZoneTLeandSensorSelect	Lead sensor selection.					
		Parameter name	**Description**			**Value**	
		TLST_LEAD	Temperature value transmitted via Modbus			1	
		TLST_T4	Temperature measured by T4 sensor (room temperature)			3	
		TLST_CONTROLLER	Temperature measured by internal controller sensor			4	
0x906	ZoneSensorOffset	Zone sensor Offset.					
		Parameter name	**Description**	**Min**	**Max**	**Step**	**Multiplier**
		LEAD_SENSOR_TEMP_OFFSET	Temperature sensor offset.	−100	100	5	0.1
0x907	T4SensorOffset	T4 average sensor offset.					
		Parameter name	**Desccription**	**Min**	**Max**	**Step**	**Multiplier**
		LEAD_SENSOR__TEMP_OFFSET	Temperature sensor offset	−100	100	5	0.1
0x908	ZoneExternalSignalEnable	Zone signal handling.					
		Parameter name	**Description**	**Value**			

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☏ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

16

		OFF_0	Disabled	0	
		ON_1	Enabled	1	
0x909	ZoneExternalSignalDrvUid	External signal drv UID			

Parameter name	Description	Min	Max
RANGE_1_31	Range 1-31	1	31

0x90A	TLeadVal	Lead temperature sensor value.				

Parameter name	Desscription	Min	Max	Step	Multiplier
LEAD_SENSOR_TEMP	Lead temperature sensor value.	-600	600	5	0.1

1.7.2. Holding Register – Static info (T box Zone settings)

Address	Name	Description
0x910	FirstZoneRegisters	First zone parameters From 0x910 to 0x91F Registers list according to 1.7.1
0x920	SecondZoneRegisters	First zone parameters From 0x920 to 0x92F Registers list according to 1.7.1
0xB00	LastZoneRegisters	First zone parameters From 0xB00 to 0xB0F Registers list according to 1.7.1

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☐ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

17

1.7.3. Input Register (T box Zone settings)

Address	Name	Description
0x900	ZoneID1	Zone ID1 	Parameter name	Description	Min	Max
---	---	---	---
RANGE_1_31	Range 1-31	1	31	
0x901	AverageZoneTemp	Average temperature measured by local temperature sensors in the zone. | Parameter name	Desccription	Min	Max	Step	Multiplier
---	---	---	---	---	---
TEMPERATURE	Temperature.	-1500	2000	5	0.1
SHORT_CIRCUIT	Short circuit			28672	
PT1000_NC	Sensor not connected.			32767		
0x902	ZoneDeviceCount	Zone devices count. 	Parameter name	Description	Min	Max
---	---	---	---
RANGE_0_31	Count in range 0-31	0	31	
0x910	ZoneID2	ZoneID2 From 0x910 to 0x912
0x920	ZoneID3	ZoneID2 From 0x920 to 0x922
0xA32	ZoneID31	ZoneID31 From 0xA32 to 0xA34

1.7.4. Holding Register - Dynamic Info T box Zone (DRV's HoldingRegisters)

Address	Name	Description
0x2300	SetZoneID	Set Zone ID that indicates in what zone device settings shall be changed.

Parameter name	Description	Min	Max
RANGE_1_31	Range 1-13	1	31

Address	Name	Description
0x2301	SetDeviceGroupID	Set device group ID that idicates what device group shall be changed in selected zone. (e.g. heaters 1793 in first zone).

Parameter name	Description	Min	Max
INFO_MAP_RANGE	Shift	0	65535

Parameter name	Description	Value
OXEN	OXEN	257
CURTAIN	CURTAIN	513
KM	KM	769
HEATER_EC	HEATER_EC	1025
DESTRATIFICATOR_AC	DESTRATIFICATOR	1281
DESTRATIFICATOR_EC	DESTRATIFICATOR_EC	1283
CURTAIN_HEATER	CURTAIN_HEATER	1537
HEATER_AC	HEATER_AC	1793
HEATER_AC_EL	HEATER_AC_EL	1794
KM_RAW	KM_RAW	2305
ROBUR_PN	ROBUR_PN	2561
COOL	COOL	2817
ROBUR_KM	ROBUR_KM	4097
ROBUR_KM_NEXT	ROBUR_KM_NEXT	4098
ROBUR	ROBUR	4353
ROBUR_NEXT	ROBUR_NEXT	4354
DRV_V_RAW	DRV_V_RAW	4865
PSENS_ABS	PSENS ABSOLUTE	5121
PSENS_DIFF	PSENS DIFFERENTIAL	5122
PSENS_DIF_60	PSENS DIFFERENTIAL 60mBar	5123
CUBE	CUBE	5377
LUNA	LUNA	5890
ELIS AX	ELIS AX	6146

Address	Name	Description
0x2302 - 0x2319	DRVregisters	DRV registers map is starting from 0x00

1.8. T box Zone(Space for Static Info)

1.8.1. Holding/Input Register - Static Info (DRV's space for Holding/Input Registers)

Name	Description				
FirstDRV	First DRV (First group detected by T-box ZONE)				
	Address space	**First address**	**Last address**	**lenght**	**repeat**
	Input registers	0x0140	0x017F	32	31
	Holding registers	0x2320	0x233F	32	31
SecondDRV	Second DRV (Second group detected by T-box ZONE)				
	Address space	**First address**	**Last address**	**lenght**	
	Input registers	0x0160	0x019F	32	
	Holding registers	0x2340	0x235F	32	
…DRV	… DRV (Next group detected by T-box ZONE)				
Thirty first DRV	Thirty first DRV				
	Address space	**First address**	**Last address**	**lenght**	
	Input registers	0x0840	0x087F	32	
	Holding registers	0x26C0	0x26DF	32	

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

20

2. Devices

2.1. Software Type

Parameter name	Description	Value
OXEN	OXEN	257
CURTAIN	CURTAIN	513
KM	KM	769
HEATER_EC	HEATER_EC	1025
DESTRATIFICATOR_AC	DESTRATIFICATOR	1281
DESTRATIFICATOR_EC	DESTRATIFICATOR_EC	1283
CURTAIN_HEATER	CURTAIN_HEATER	1537
HEATER_AC	HEATER_AC	1793
HEATER_AC_EL	HEATER_AC_EL	1794
KM_RAW	KM_RAW	2305
ROBUR_PN	ROBUR_PN	2561
COOL	COOL	2817
ROBUR_KM	ROBUR_KM	4097
ROBUR_KM_NEXT	ROBUR_KM_NEXT	4098
ROBUR	ROBUR	4353
ROBUR_NEXT	ROBUR_NEXT	4354
DRV_V_RAW	DRV_V_RAW	4865
PSENS_ABS	PSENS ABSOLUTE	5121
PSENS_DIFF	PSENS DIFFERENTIAL	5122
PSENS_DIF_60	PSENS DIFFERENTIAL 60mBar	5123
CUBE	CUBE	5377
LUNA	LUNA	5890
ELIS AX	ELIS AX	6146

2.2. DRV-ELIS & DRV-SLIM (Air Curtain)

2.2.1. INPUT REGISTER DRV ELIS/SLIM

Address	Name	Description
0x01	Software_type	

Parameter	Description	Value
CURTAIN	CURTAIN	513

Address	Name	Description
0x02	Connection count	Register for internal use.
0x03	Soft_ver	Register for internal use.
0x04	T3	Temperature measured by T3 sensor (air after water heat exchanger).

Value	Temperature [C]	Description	Alarm
-350	-35,0	Minimal value	
350	35,0	Maximal value	
0x7000	-	Short circuit	
0x7FFF	-	PT1000 sensor not connected	**ALARM**

Address	Name	Description
0x05	T4	Temperature measured by T4 sensor (air before water heat exchanger).

Value	Temperature [C]	Description	Alarm
-350	-35,0	Minimal value	
350	35,0	Maximal value	
0x7000	-	Short circuit	
0x7FFF	-	PT1000 sensor not connected	**ALARM**

Address	Name	Description
0x06	CurtainFanSpeed	Curtain fan speed (S1, S2, S3). *AC Fan - 3 steps.*

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

Address	Name	Description
0x07	ValveState	Valve state

Value	Name	Description
0x00	VALVE_IDLE	Valve in stand by mode (for 3-way valves)
0x01	VALVE_OPEN	Opening valve
0x02	VALVE_CLOSE	Closing valve

Address	Name	Description
0x08	HeaterFanSpeed	Heater fan speed (S1, S2, S3). *AC Fan - 3 steps.*

Value	Name	Description
0x00	VALVE_IDLE	Valve in stand by mode (for 3-way valves)
0x01	VALVE_OPEN	Opening valve

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

22

Address	Name	Description			
		0x02	VALVE_CLOSE		Closing valve
0x09	ContactDoor	Contact door state.			
		Value	Name		Description
		0x01	DOOR_OPEN		Door open
		0x02	DOOR_CLOSE		Door close
0x0A	HeaterDetect	Heater detection procedure (ELIS-DUO).			
		Value	Name		Description
		0x00	HEATER_DT_NS		Detection procedure not commenced
		0x01	HEATER_DT_FAIL		Heater not detected
		0x02	HEATER_DT_PASS		Heater detected

0x0B — AntifreezeeState — Information about antifreeze (8 bits for respected mode).

Value 15..8 bit	Value 7..0 bit	Antifreeze	Description	Alarm
-	0x01	Warehouse	Normal work mode.	
-	0x02	Warehouse	Antifreeze enabled (user parameters overwritten)	**ALARM**
0x01	-	Water Exchanger	Normal work mode.	
0x02	-	Water Exchanger	Antifreeze enabled (user parameters overwritten)	**ALARM**

0x0C — FuseState — Fuse state for 3V fans, information can be read from 4 bits (11..8 bit).

Value 11..8 bit	Description	Alarm
0x00	Read only	
0x01	Fuse state - working	
0x02	Fuse state - blown	**ALARM**

Example:

Fuse state 3V fan: working (0x1)

Register value: 0x100

Fuse state 3V fan: blown (0x2)

Register value: 0x200

0x0D — CurtainElectricpower — Electric heater power.

Value	Name	L2 output	L1 output
0x00	ELECTRIC_POWER_0	OFF	OFF
0x01	ELECTRIC_POWER_1	OFF	ON

L1, L2 outputs are located on VALVE connector.

2.2.2. HOLDING REGISTER DRV ELIS/SLIM

Address	Name	Description
0x00	WorkMode	Work mode

Value	Work status	Description
0	WM_TS	From local TS regulator
1	WM_OFF	Device off
2	WM_HEAT	Heat mode
3	WM_VENT	Ventilation mode

Address	Name	Description
0x01	CurtainFanSpeedRef	Forcing fan speed (S1, S2, S3). *AC Fan - 3 steps.*

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

Address	Name	Description
0x02	NULL_2	Register not used.
0x03	NULL_3	Register not used.
0x04	CurtainProgram	Device group ID Curtain program setting.

Value	Setting	Description
0	CURT_PRG_NS	No forcing
1	CURT_PRG_K1	Forcing SW3 to value K1 (Temp. Drop or Door Switch Turns On Unit)
2	CURT_PRG_K2	Forcing SW3 to value K2 (Door Switch Turns On unit, Than temp. Drop Turns On Heating)

Address	Name	Description
0x05	CurtainFanIdleRef	Stand-by fan operation. *AC Fan - 3 steps.*

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

Step:1

Multiplier: 1,0

Address	Name	Description
0x06	FanIdleDelay	Time delay of stand-by fan operation. **Value / Description** 0..65534 — Delay in seconds 65535 — Infinite **Step:1** **Multiplier: 1,0**

Detailed Description for 0x06 FanIdleDelay:

Time delay of stand-by fan operation.

Value	Description
0..65534	Delay in seconds
65535	Infinite

Step:1

Multiplier: 1,0

0x07 — ValveIdleDelay

Time delay of valve in stand-by fan operation.

Value	Description
0..65534	Delay in seconds
65535	Infinite

Condition: ValveIdleDelay<FanIdleDelay

Step:1

Multiplier: 1,0

0x08 — AntifreezeWaterExchanger State

Information about water exchanger antifreeze.

Value	Name	Description
0x00	NOT_SET	Not set
0x01	ON_1	enabled
0x02	OFF_2	disabled

0x09 — AntifreezeWaterExchanger TempRef

Target temperature to enable antifreeze.

Value	Temperature [C]	Description
50	5,0°C	Minimal value
150	15,0°C	Maximal value

Step:5

Multiplier: 0,1

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☐ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

25

2.3. DRV D (LEO D - destratifier)

2.3.1. INPUT REGISTER DRV D

Address	Name	Description
0x01	Software_type	<table><tr><td>**Parameter**</td><td>**Description**</td><td>**Value**</td></tr><tr><td>CURTAIN</td><td>CURTAIN</td><td>1281</td></tr></table>
0x02	Connection count	Register for internal use
0x03	Soft_ver	Register for internal use
0x04	T3	Temperature measured by T3 sensor (temperature measured near the celling). <table><tr><td>**Value**</td><td>**Temperature [C]**</td><td>**Description**</td><td>**Alarm**</td></tr><tr><td>-350</td><td>-35,0</td><td>Minimal value</td><td></td></tr><tr><td>350</td><td>35,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>**ALARM**</td></tr></table>
0x05	T4	Temperature measured by T4 sensor (temperature measured in the room). <table><tr><td>**Value**</td><td>**Temperature [C]**</td><td>**Description**</td><td>**Alarm**</td></tr><tr><td>-350</td><td>35,0</td><td>Minimal value</td><td></td></tr><tr><td>350</td><td>35,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>**ALARM**</td></tr></table>
0x06	FanEff	Curtain fan speed (S1, S2, S3). *AC Fan - 3 steps.* <table><tr><td>**Value**</td><td>**Gear**</td><td>**Description**</td></tr><tr><td>0</td><td>FAN_SPEED0</td><td>Fan off</td></tr><tr><td>1..33</td><td>FAN_SPEED1</td><td>First step</td></tr><tr><td>34..66</td><td>FAN_SPEED2</td><td>Second step</td></tr><tr><td>67..100</td><td>FAN_SPEED3</td><td>Third step</td></tr></table>
0x07	DestStatus	Desertification condition. <table><tr><td>**Value**</td><td>**Description**</td></tr><tr><td>0x01</td><td>Condition (destTemp > Td - Tm) and (Tz > Tm) not met</td></tr><tr><td>0x02</td><td>Condition (destTemp > Td - Tm) and (Tz > Tm) met</td></tr></table> *Tz* - target room temperature (Tref) *Td* - temperature measured near the celling (T3 sensor), *Tm* - temperature measured in the room (TLeadVal or T4 sensor - depends on *TleadSensorSelect* settings).

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

26

Address	Name	Description
0x08	FuseState	Fuse state for 3V fans, information can be read from 4 bits (11..8 bit).

Value 11..8 bit	Description	Alarm
0x00	Read only	
0x01	Fuse state - working	
0x02	Fuse state - blown	**ALARM**

Example:

Fuse state 3V fan: working (0x1)

Register value: 0x100

Fuse state 3V fan: blown (0x2)

Register value: 0x200

2.3.2. HOLDING REGISTER DRV D

Address	Name	Description
0x00	WorkMode	Work mode

Value	Work state	Name	Description
1	WM_OFF	HEATER_DT_NS	Desertification off
2	WM_AUTO_DEPEND		Work mode AUTO
4	WM_MANUAL	HEATER_DT_PASS	Work mode MANUAL

Address	Name	Description
0x01	FanEffRef	Fan efficiency setting. *AC Fan - 3 steps.*

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

Address	Name	Description
0x02	DestTempRef	Target value for lunching desertification mode.

Value	Temperature [K]	Description
0	0,0	Minimal value
50	5,0	Default value
100	10,0	Maximal value

Condition:

DestTempRef > Td – Tm

Td – temperature value measured near desertificator (*T3* sensor).

Tm – temperature value measured in the room (*TLeadVal* or *T4* - depends on the *TleadSensorSelect* register value).

Address	Name	Description
0x03	WorkModeTempR ef	Target value for desertification in MANUAL mode.

Value	Temperature [C]	Description
50	5,0	Minimal value
450	45,0	Maximal value

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

28

2.4. DRV M (LEO EC – Fan Heater)

2.4.1. INPUT REGISTER DRV M

Address	Name	Description
0x01	Software_type	

Parameter	Description	Value
HEATER_EC	HEATER_EC	1025

Address	Name	Description
0x02	Connection count	Register for internal use
0x03	Soft_ver	Register for internal use
0x04	T3	Temperature measured by T3 sensor (air after water heat exchanger).

Value	Temperature [C]	Description	Alarm
–500	–50,0	Minimal value	
1000	100,0	Maximal value	
0x7000	–	Short circuit	
0x7FFF	–	PT1000 sensor not connected	**ALARM**

Address	Name	Description
0x05	T4	Temperature measured by T4 sensor (temperature measured in the room).

Value	Temperature [C]	Description	Alarm
–500	–50,0	Minimal value	
1000	100,0	Maximal value	
0x7000	–	Short circuit	
0x7FFF	–	PT1000 sensor not connected	**ALARM**

Address	Name	Description
0x06	FanEff	*EC Fan* - Revolutions per minute (rpm).

Value [rpm]	Description
0	Minimal value
3000	Maximal value

Address	Name	Description
0x07	AntifreezeeState	Information about antifreeze (8 bits for respected mode).

Value 15..8 bit	Value 7..0 bit	Antifreeze	Description	Alarm
–	0x01	Warehouse	Normal work mode.	
–	0x02	Warehouse	Antifreeze enabled (user parameters overwritten)	**ALARM**
0x01	–	Water Exchanger	Normal work mode.	
0x02	–	Water Exchanger	Antifreeze enabled (user parameters overwritten)	**ALARM**

Address	Name	Description
0x08	DestStatus	Destratification status: *(destDtemp > Td – Tm) and (Tz >Tm)* *Tz* – room setting temp. (value from Tref register) *Td* – temp. measured at destratificator (temp. value from T3 sensor) *Tm* – temp. measured into room (value from TLeadVal or T4 - depending on settings in TleadSensorSelect register)

0x08 DestStatus table (continued):

Value	Description
0x01	Condition (destDtemp > Td – Tm) and (Tz >Tm) not fullfilled
0x02	Condition (destDtemp > Td – Tm) and (Tz >Tm) fullfilled

Address	Name	Description
0x09	FanEcConnect	EC Fan and DRV M connection status.

Value	Description	Alarm
0x01	Fan not connected	**ALARM**
0x02	Fan connected	

Address	Name	Description
0x0A	FuseState	Fuse state for EC/3V/Roof fans, information can be read from 4 bits.

Bit	Description
3..0	Roof fan
4..7	EC fan
8...11	3V fan

Value	Description	Alarm
0x00	Read only	
0x01	Fuse state – working	
0x02	Fuse state – blown	**ALARM**

Example:

Fuse state 3V fan: working (0x1)

Register value: 0x100

Fuse state 3V fan: blown (0x2)

Register value: 0x200

Address	Name	Description
0x0B	ValveState	Valve state.

Value	Name	Description
0x00	VALVE_IDLE	Valve in stand by mode (for 3-way valves)
0x01	VALVE_OPEN	Opening valve
0x02	VALVE_CLOSE	Closing valve

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

30

2.4.2. HOLDING REGISTER DRV M

Address	Name	Description
0x00	WorkMode	Work mode.

Value	Work state	Description
0	WM_DEF	Default value after power reset
1	WM_OFF	Device off
2	WM_HT_AUTO	Automatic heating
3	WM_HT_MANUAL	Manual heating
4	WM_COOL_AUTO	Automatic cooling
5	WM_COOL_MANUAL	Manual cooling
6	WM_VENT	Ventilation

Address	Name	Description
0x01	FanEffRef	Fan efficiency setting.

Value	Efficeincy [%]	Description
0	0	Minimum value
100	100	Maximum value

Address	Name	Description
0x02	DestEnable	Forcing destratification mode for destratificator

Value	Description
1	Disabled
2	Enabled

Address	Name	Description
0x03	DestTempRef	Target value for lunching desertification mode.

Value	Temperature [K]	Description
0	0,0	Minimal value
50	**5,0**	**Default value**
100	10,0	Maximal value

Condition:

$DestTempRef > Td - Tm$

Td – temperature value measured near desertificator (T3 sensor).

Tm – temperature value measured in the room (TLeadVal or T4 - depends on the *TleadSensorSelect* register value).

Address	Name	Description
0x04	NULL_4	Register not used.
0x05	ModeAutoFanEffRefMin	Minimal fan efficiency in AUTO mode.

Value	Efficeincy [%]	Description
0	0	Minimum value
100	100	Maximum value

Address	Name	Description
0x06	ModeAutoFanEffRefMax	Maximal fan efficiency in AUTO mode.

Value	Efficeincy [%]	Description
0	0	Minimum value
100	100	Maximum value

Address	Name	Description			
0x07	ModeManualFannEffRef	Fan efficiency after attaining target temperature in MANUAL mode.			
		Value	**Efficeincy [%]**	**Description**	
		0	0	Minimum value	
		100	100	Maximum value	

2.5. DRV V (LEO AC – Fan Heater)

2.5.1. INPUT REGISTER DRV V

Address	Name	Description			
0x01	Software_type				
		Parameter	**Description**	**Value**	
		LEO V	LEO AC (HEATER AC)	1793	
0x02	Connection count	Register for internal use			
0x03	Soft_ver	Register for internal use			
0x04	T3	Temperature measured by T3 sensor (temperature measured near the celling).			
		Value	**Temperature [C]**	**Description**	**Alarm**
		−500	−50,0	Minimal value	
		1000	100,0	Maximal value	
		0x7000	−	Short circuit	
		0x7FFF	−	PT1000 sensor not connected	**ALARM**
0x05	T4	Temperature measured by T4 sensor (room temperature).			
		Value	**Temperature [C]**	**Description**	**Alarm**
		−500	−50,0	Minimal value	
		1000	100,0	Maximal value	
		0x7000	−	Short circuit	
		0x7FFF	−	PT1000 sensor not connected	**ALARM**
0x06	FanEff	*AC Fan - 3 steps.*			
		Value	**Gear**	**Description**	
		0	**FAN_SPEED0**	**Fan off**	
		1..33	FAN_SPEED1	First step	
		34..66	FAN_SPEED2	Second step	
		67..100	FAN_SPEED3	Third step	

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

32

Address	Name	Description
0x07	AntifreezeeState	Warehouse antifreeze state.

Value	Description	Alarm
0x01	Normal work mode.	
0x02	Antifreeze enabled (user parameters overwritten).	**ALARM**

Address	Name	Description
0x08	DestStatus	Destratification status: $(destDtemp > Td - Tm)$ and $(Tz > Tm)$ Tz – room setting temp. (value from Tref register) Td – temp. measured at destratificator (temp. value from T3 sensor) Tm – temp. measured into room (value from TLeadVal or T4 – depending on settings in TleadSensorSelect register)

Value	Description
0x01	Condition $(destDtemp > Td - Tm)$ and $(Tz > Tm)$ not fullfilled
0x02	Condition $(destDtemp > Td - Tm)$ and $(Tz > Tm)$ fullfilled

Address	Name	Description
0x09	FilterPressureState	Filter pressure state.

Value	Description
0x00	Filter – bad condition, or not connected
0x02	Filter – good condition, connected

Address	Name	Description
0x0A	FuseState	Fuse state for EC/3V/Roof fans, information can be read from 4 bits.

Bit	Description
3..0	Roof fan
4..7	EC fan
8...11	3V fan

Value	Description	Alarm
0x00	Read only	
0x01	Fuse state - working	
0x02	Fuse state - blown	**ALARM**

Example:

Fuse state 3V fan: working (0x1)

Register value: 0x100

Fuse state 3V fan: blown (0x2)

Register value: 0x200

Address	Name	Description
0x0B	ValveState	Valve state.

0x00	VALVE_IDLE	Valve in stand by mode (for 3-way valves)
0x00	VALVE_IDLE	Valve in stand by mode (for 3-way valves)
0x01	VALVE_OPEN	Opening valve
0x02	VALVE_CLOSE	Closing valve

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

33

2.5.2. HOLDING REGISTER DRV V

Address	Name	Description
0x00	WorkMode	Work mode.

Work mode table:

Value	Work state	Description
0	WM_DEF	Default value after power reset
1	WM_OFF	Device off
2	WM_HT_AUTO	Automatic heating
3	WM_HT_MANUAL	Manual heating
4	**WM_COOL_AUTO**	**Automatic cooling**
5	WM_COOL_MANUAL	Manual cooling
6	WM_VENT	Ventilation

Address	Name	Description
0x01	FanEffRef	Fan efficiency setting. *AC Fan - 3 steps.*

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

Address	Name	Description
0x02	DestEnable	Forcing destratification mode for destratificator

Value	Description
1	Disabled
2	Enabled

Address	Name	Description
0x03	DestTempRef	Target value for lunching desertification mode.

Value	Temperature [K]	Description
0	0,0	Minimal value
50	**5,0**	**Default value**
100	10,0	Maximal value

Condition:

DestTempRef > Td – Tm

Td – temperature value measured near desertificator (T3 sensor).

Tm – temperature value measured in the room (TLeadVal or T4 - depends on the *TleadSensorSelect* register value).

Address	Name	Description
0x04	NULL_4	Register not used.
0x05	ModeAuto_FanEffRef Min	Minimal fan efficiency and fan efficiency after attaining target temperature in AUTO mode. *AC Fan - 3 steps.*

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📞 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

34

Address	Name	Description			
			34..66	FAN_SPEED2	Second step
			67..100	FAN_SPEED3	Third step
0x06	ModeManual_FanEffR ef	Fan efficiency after attaining target temperature in MANUAL mode. *AC Fan - 3 steps.*			

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

35

2.6. DRV COOL (LEO COOL – Fan Heater)

2.6.1. INPUT REGISTER DRV COOL

Address	Name	Description
0x01	Software_type	<table><tr><td>Parameter</td><td>Description</td><td>Value</td></tr><tr><td>COOL</td><td>COOL</td><td>2817</td></tr></table>
0x02	Connection count	Register for internal use
0x03	Soft_ver	Register for internal use
0x04	T3	Temperature measured by T3 sensor (temperature measured near the celling). <table><tr><td>Value</td><td>Temperature [C]</td><td>Description</td><td>Alarm</td></tr><tr><td>-500</td><td>-50,0</td><td>Minimal value</td><td></td></tr><tr><td>1000</td><td>100,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>
0x05	T4	Temperature measured by T4 sensor (room temperature). <table><tr><td>Value</td><td>Temperature [C]</td><td>Description</td><td>Alarm</td></tr><tr><td>-500</td><td>-50,0</td><td>Minimal value</td><td></td></tr><tr><td>1000</td><td>100,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>
0x06	FanEff	*AC Fan - 3 steps.* <table><tr><td>Value</td><td>Gear</td><td>Description</td></tr><tr><td>**0**</td><td>**FAN_SPEED0**</td><td>**Fan off**</td></tr><tr><td>1..33</td><td>FAN_SPEED1</td><td>First step</td></tr><tr><td>34..66</td><td>FAN_SPEED2</td><td>Second step</td></tr><tr><td>67..100</td><td>FAN_SPEED3</td><td>Third step</td></tr></table>
0x07	AntifreezeeState	Warehouse antifreeze state. <table><tr><td>Value</td><td>Description</td><td>Alarm</td></tr><tr><td>0x01</td><td>Normal work mode.</td><td></td></tr><tr><td>0x02</td><td>Antifreeze enabled (user parameters overwritten).</td><td>ALARM</td></tr></table>
0x08	NULL_8	Register not used.
0x09	FilterPressureState	Filter pressure state. <table><tr><td>Value</td><td>Description</td></tr><tr><td>0x00</td><td>Filter – bad condition, or not connected</td></tr><tr><td>0x02</td><td>Filter – good condition, connected</td></tr></table>

Address	Name	Description
0x0A	FuseState	Fuse state for EC/3V/Roof fans, information can be read from 4 bits.

Bit	Description
3..0	Roof fan
4..7	EC fan
8...11	3V fan

Value	Description	Alarm
0x00	Read only	
0x01	Fuse state - working	
0x02	Fuse state - blown	**ALARM**

Example:

Fuse state 3V fan: working (0x1)

Register value: 0x100

Fuse state 3V fan: blown (0x2)

Register value: 0x200

Address	Name	Description
0x0B	ValveState	Valve state.

0x00	VALVE_IDLE	Valve in stand by mode (for 3-way valves)
0x00	VALVE_IDLE	Valve in stand by mode (for 3-way valves)
0x01	VALVE_OPEN	Opening valve
0x02	VALVE_CLOSE	Closing valve

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

37

2.6.2. HOLDING REGISTER DRV COOL

Address	Name	Description
0x00	WorkMode	Work mode.

<table>
<tr><th>Value</th><th>Work state</th><th>Description</th></tr>
<tr><td>0</td><td>WM_DEF</td><td>Default value after power reset</td></tr>
<tr><td>1</td><td>WM_OFF</td><td>Device off</td></tr>
<tr><td>2</td><td>WM_HT_AUTO</td><td>Automatic heating</td></tr>
<tr><td>3</td><td>WM_HT_MANUAL</td><td>Manual heating</td></tr>
<tr><td>4</td><td>WM_COOL_AUTO</td><td>Automatic cooling</td></tr>
<tr><td>5</td><td>WM_COOL_MANUAL</td><td>Manual cooling</td></tr>
<tr><td>6</td><td>WM_VENT</td><td>Ventilation</td></tr>
</table>

0x01 — FanEffRef

Fan efficiency setting.

AC Fan - 3 steps.

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

Address	Name	Description
0x02	NULL_2	Register not used.
0x03	NULL_3	Register not used.
0x04	NULL_4	Register not used.

0x05 — ModeAuto_FanEffRef Min

Minimal fan efficiency and fan efficiency after attaining target temperature in AUTO mode.

AC Fan - 3 steps.

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

0x06 — ModeManual_FanEffR ef

Fan efficiency after attaining target temperature in MANUAL mode.

AC Fan - 3 steps.

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

38

![FLOWAIR intelligent air flow]

2.7. DRV EL (LEO EL – Electric Fan Heater)

2.7.1. INPUT REGISTER DRV EL

Address	Parameter	Description
0x01	Software_type	<table><tr><td>**Parameter**</td><td>**Description**</td><td>**Value**</td></tr><tr><td>HEATER_AC_EL</td><td>HEATER_AC_EL</td><td>1794</td></tr></table>
0x02	Connection count	Register for internal use
0x03	Soft_ver	Register for internal use
0x04	T3	Temperature measured by T3 sensor (temperature measured near the celling). <table><tr><td>**Value**</td><td>**Temperature [C]**</td><td>**Description**</td><td>**Alarm**</td></tr><tr><td>-500</td><td>-50,0</td><td>Minimal value</td><td></td></tr><tr><td>1000</td><td>100,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>**ALARM**</td></tr></table>
0x05	T4	Temperature measured by T4 sensor (room temperature). <table><tr><td>**Value**</td><td>**Temperature [C]**</td><td>**Description**</td><td>**Alarm**</td></tr><tr><td>-500</td><td>-50,0</td><td>Minimal value</td><td></td></tr><tr><td>1000</td><td>100,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>**ALARM**</td></tr></table>
0x06	FanEff	Fan efficiency. *AC Fan - 3 steps.* <table><tr><td>**Value**</td><td>**Gear**</td><td>**Description**</td></tr><tr><td>**0**</td><td>**FAN_SPEED0**</td><td>**Fan off**</td></tr><tr><td>1..33</td><td>FAN_SPEED1</td><td>First step</td></tr><tr><td>34..66</td><td>FAN_SPEED2</td><td>Second step</td></tr><tr><td>67..100</td><td>FAN_SPEED3</td><td>Third step</td></tr></table>
0x07	AntifreezeeState	Information about antifreeze. <table><tr><td>**Value**</td><td>**Description**</td><td>**Alarm**</td></tr><tr><td>0x01</td><td>Normal work mode.</td><td></td></tr><tr><td>0x02</td><td>Antifreeze enabled (user parameters overwritten).</td><td>**ALARM**</td></tr></table>

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia NIP: 9581440661 58 627 57 20 info@flowair.pl www.flowair.com

T-BOX Zone Modbus RTU V4.7.docx
39

Address	Parameter	Description
0x08	DestStatus	Destratification status: *(destDtemp > Td - Tm) and (Tz >Tm)* *Tz* - room setting temp. (value from Tref register) *Td* - temp. measured at destratificator (temp. value from T3 sensor) *Tm* - temp. measured into room (value from TLeadVal or T4 - depending on settings in *TleadSensorSelect* register
0x09	ThermalContactState	hermal contact state.
0x0A	FuseState	Fuse state for EC/3V/Roof fans, information can be read from 4 bits.

0x08 DestStatus:

Value	Description
0x01	Condition (destDtemp > Td - Tm) and (Tz >Tm) not fullfilled
0x02	Condition (destDtemp > Td - Tm) and (Tz >Tm) fullfilled

0x09 ThermalContactState:

Value	Description	Alarm
0x01	Overheat alarm	**ALARM**
0x02	Normal work	

IF 0x09 = 0x01 user parameters are overwritten:

    HR 0x07 FanEffRef = 100

    HR 0x0F ElectricHeaterPTCPower = 0

Overwrite discontinues when temperature inside the heater drops below safe limits.

0x0A FuseState:

Bit	Description
3..0	Roof fan
4..7	EC fan
8...11	3V fan

Value	Description	Alarm
0x00	Read only	
0x01	Fuse state - working	
0x02	Fuse state - blown	**ALARM**

Example:

Fuse state 3V fan: working (0x1)

Register value: 0x100

Fuse state 3V fan: blown (0x2)

Register value: 0x200

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📞 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

40

Address	Parameter	Description
0x0B	PTCHeaterPowerState	Electric heater power for LEO EL L in manual heating work mode. (SW3.5 = K1)
0x0C	ElectricHeaterTyper	

Electric heater power for LEO EL L in manual heating work mode.

(SW3.5 = K1)

Value	L2 State	L1 State	Description
0x01	**OFF**	**OFF**	**Off**
0x02	OFF	ON	1 heat setting
0x03	ON	OFF	2 heat setting
0x04	ON	ON	3 heat setting

Electric heater power for LEO EL S in manual heating work mode.

(SW3.5 = K2)

Value	L2 State	L1 State	Description
0x01	**OFF**	**OFF**	**Off**
0x02	OFF	ON	1 heat setting
0x03	ON	ON	2 heat setting
0x04	ON	ON	2 heat setting

Value	L2 State	Description
0x01	EH_TYPE_EL10	LEO EL S heater
0x02	EH_TYPE_EL23	LEO EL L heater

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

41

2.7.2. HOLDING REGISTER DRV EL

Address	Name	Description
0x00	WorkMode	Work mode.
			Value	Work status	Description
---	---	---	---
			0x00	WM_TS	**(Local controll by only TS regulator)**
			0x01	WM_OFF	Device off
			0x02	WM_AUTO	Automatic mode
			0x03	WM_HEAT	Manual heating
			0x04	WM_VENT	Ventilation
			0x05	WM_RAW	Raw. *Not used.*
0x01	FanSpeedRef	Fan efficiency setting. *AC Fan - 3 steps.*
			Value	Gear	Description
			0	FAN_SPEED0	**Fan off**
			1..33	FAN_SPEED1	First step
			34..66	FAN_SPEED2	Second step
			67..100	FAN_SPEED3	Third step
0x02	DestTempRef	Target value for lunching desertification mode.
			Value	Temperature [K]	Description
			0	0,0	Minimal value
			50	**5,0**	**Default value**
			100	10,0	Maximal value
		Condition: $DestTempRef > Td - Tm$ Td – temperature value measured near desertificator (T3 sensor). Tm – temperature value measured in the room (TLeadVal or T4 - depends on the *TleadSensorSelect* register value).
0x04	NULL_4	Register not used.
0x05	ElectricHeaterPTCPowerL	Electric heater power for LEO EL L in manual heating work mode. (SW3.5 = K1)
			Value	L2 State	L1 State	Description
			0x01	**OFF**	**OFF**	**Off**
			0x02	OFF	ON	1 heat setting
			0x03	ON	OFF	2 heat setting
			0x04	ON	ON	3 heat setting

Address	Name	Description
0x06	ElectricHeaterPTCPowerS	Electric heater power for LEO EL S in manual heating work mode. (SW3.5 = K2)

Value	L2 State	L1 State	Description
0x01	**OFF**	**OFF**	**Off**
0x02	OFF	ON	1 heat setting
0x03	ON	ON	2 heat setting
0x04	ON	ON	2 heat setting

Address	Name	Description
0x07	ModeAuto_FanEffRefMin	Minimal fan efficiency and fan efficiency after attaining target temperature in AUTO mode. *AC Fan - 3 steps.*

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

Address	Name	Description
0x08	ModeManual_FanEffRef	Fan efficiency after attaining target temperature in MANUAL mode. *AC Fan - 3 steps.*

Value	Gear	Description
0	**FAN_SPEED0**	**Fan off**
1..33	FAN_SPEED1	First step
34..66	FAN_SPEED2	Second step
67..100	FAN_SPEED3	Third step

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

43

2.8. DRV R (ROBUR NEXT R – Gas Heater)

2.8.1. INPUT REGISTER DRV R

Address	Parameter	Description
0x01	Software_type	

Parameter	Description	Value
ROBUR_R_NEXT	ROBUR_R_NEXT	4354

Address	Parameter	Description
0x02	Connection count	Register for internal use
0x03	Soft_ver	Register for internal use
0x04	NULL_04	Register not used.
0x05	T3	Temperature measured by T3 sensor (temperature measured near the celling).

Value	Temperature [C]	Description	Alarm
–500	–50,0	Minimal value	
1000	100,0	Maximal value	
0x7000	–	Short circuit	
0x7FFF	–	PT1000 sensor not connected	**ALARM**

Address	Parameter	Description
0x06	T4	Temperature measured by T4 sensor (room temperature).

Value	Temperature [C]	Description	Alarm
–500	–50,0	Minimal value	
1000	100,0	Maximal value	
0x7000	–	Short circuit	
0x7FFF	–	PT1000 sensor not connected	**ALARM**

Address	Parameter	Description
0x07	NULL_7	Register not used.
0x08	ExternalGasDetectTH1	External gas detector signal - first threshold.

Value	Description	Alarm
0x00	Gas concentration below threshold	
0x01	Gas concentration exceeds threshold	**ALARM**

Address	Parameter	Description
0x09	ExternalGasDetectTH2	External gas detector signal - second threshold.

Value	Description	Alarm
0x00	Gas concentration below threshold	
0x01	Gas concentration exceeds threshold	**ALARM**

Address	Parameter	Description
0x0A	ExternalGasDetectVal	Gas concentration value - 0-10V DC input (gas detector scaling information required)
0x0B	NULL_11	Register not used.
0x0C	NULL_12	Register not used.
0x0D	NULL_13	Register not used.
0x0E	NULL_14	Register not used.

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

44

Address	Parameter	Description			
0x0F	AntifreezeStateWarehouse	Information about warehouse antifreeze state.			
		Value	**Description**		**Alarm**
		0x01	Normal work mode		
		0x02	Antifreeze enabled (user parameters overwritten)		**ALARM**
0x10	FuseState	Fan fuse state.			
		Value	**Description**		**Alarm**
		0x00	Read only		
		0x01	Fuse state - working		
		0x02	Fuse state - blown		**ALARM**
0x11	GasAlarmState	Robur alarm (gas/flame). Read from clamp no.6 (connection terminal inside Robur heater).			
		Value	**Name**	**Description**	**Alarm**
		0x01	ON	Alarm detected	**ALARM**
		0x02	OFF	No alarm	
0x12	STBAlarmState	Air extraction temperature alarm (STB).			
		Value	**Name**	**Description**	**Alarm**
		0x00	NC	PT1000 sensor not connected	**ALARM**
		0x01	ON	STB alarm detected ($T3 \geq T\_STB\_REF$)	**ALARM**
		0x02	OFF	STB alarm not detected ($T3 \leq (T\_STB\_REF - 1 [K])$)	
0x13	FilterWorkTime	Filter work time. FilterWorkTime = 5 * FilterWorkTime (min)			
		Value	**Work time (min)**		**Description**
		0	0		Minimal value
		65535	5*65535		Maximal Value

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx
45

2.8.2. HOLDING REGISTER DRV R

Address	Parameter	Description
0x00	WorkMode	Work mode.
0x08	STBTemperatureAlarm On	Target temperature to invoke STB alarm state *(Inpur Register 0x12)*. If > T3 alarm occurs. Default value ensures error occurrence before real STB Robur alarm (which needs manual reset from heater control box).
0x09	STBTemperatureAlarm Off	Target temperature to reset STB alarm state *(Inpur Register 0x12)*. If > T3 alarm occurs.
0x0A	ContinuosModeFan SpeedRef	Fan speed after attaining target temperature.
0x0B	GasBurnerLevelRef	Gas heater power in manual heating work mode.

0x00 — WorkMode

Value	Work state	Description
0x00	NS	Read only
0x01	OFF	Device off
0x02	HEAT_AUTO	Automatic heating mode
0x03	**HEAT_MANUAL**	**Manual heating mode**
0x04	VENT	Ventilation mode

0x08 — STBTemperatureAlarm On

Value	Temperature [K]	Description
810	81,0	Minimal value
900	**90,0**	**Default value**
1200	120,0	Maximal value

0x09 — STBTemperatureAlarm Off

Value	Temperature [K]	Description
610	61,0	Minimal value
800	**80,0**	**Maximal value**

Additional condition:

$STB\_T\_OFF < STB\_T\_REF$

0x0A — ContinuosModeFanSpeedRef

Value	Description
100	Fan on
0	Fan off

0x0B — GasBurnerLevelRef

Value	Description
0x00	Read only
0x01	Gas burner first step
0x02	Gas burner second step

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

46

2.9. DRV R KM (ROBUR NEXT R KM – Gas Heater with mixing Chamber)

2.9.1. INPUT REGISTER DRV R KM

Address	Parameter	Description
0x01	Software_type	

Parameter	Description	Value
ROBUR_KM_NEXT	ROBUR_KM_NEXT	4098

Address	Parameter	Description
0x02	Connection count	Register for internal use
0x03	Soft_ver	Register for internal use
0x04	T1	Temperature measured by T1 sensor (fresh air temperature).

Value	Temperature [C]	Description	Alarm
-500	-50,0	Minimal value	
1000	100,0	Maximal value	
0x7000	-	Short circuit	
0x7FFF	-	PT1000 sensor not connected	**ALARM**

Address	Parameter	Description
0x05	T3	Temperature measured by T3 sensor (air extraction temperature).

Value	Temperature [C]	Description	Alarm
-500	-50,0	Minimal value	
1000	100,0	Maximal value	
0x7000	-	Short circuit	
0x7FFF	-	PT1000 sensor not connected	**ALARM**

Address	Parameter	Description
0x06	T4	Temperature measured by T4 sensor (room temperature).

Value	Temperature [C]	Description	Alarm
-500	-50,0	Minimal value	
1000	100,0	Maximal value	
0x7000	-	Short circuit	
0x7FFF	-	PT1000 sensor not connected	**ALARM**

Address	Parameter	Description
0x07	NULL_7	Register not used.
0x08	ExternalGasDetectTH1	External gas detector signal - first threshold.

Value	Description	Alarm
0x00	Gas concentration below threshold	
0x01	Gas concentration exceeds threshold	**ALARM**

Address	Parameter	Description
0x09	ExternalGasDetectTH2	External gas detector signal - second threshold.

Value	Description	Alarm
0x00	Gas concentration below threshold	
0x01	Gas concentration exceeds threshold	**ALARM**

Address	Parameter	Description
0x0A	ExternalGasDetectVal	Gas concentration value - 0-10V DC input (gas detector scaling information required)

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☐ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

47

Address	Parameter	Description		
0x0B	NULL_11	Thermocontact signal from fan roof.		

Value	Description	Alarm
0x01	Temperature below safe limit	
0x02	Temperature above safe limit	**ALARM**

Address	Parameter	Description
0x0C	NULL_12	Roof fan efficiency.

Value	Description
0	Minimal value
100	Maximal value

Address	Parameter	Description
0x0D	DamperLevel	Damper position.

Value	Description	Alarm
0x01	Temperature below safe limit	
0x02	Temperature above safe limit	**ALARM**

Address	Parameter	Description
0x0E	DamperForceState	Forcing state for damper in mode DamperForceMode == DAMPER_FMD_ON

Value	Condition
0x01	T4 >= DamperForceTempRef
0x02	T4 < DamperForceTempRef

Address	Parameter	Description
0x0F	AntifreezeStateWarehouse	Information about warehouse antifreeze state.

Value	Description	Alarm
0x01	Normal work mode	
0x02	Antifreeze enabled (user parameters overwritten)	**ALARM**

Address	Parameter	Description
0x10	FuseState	Fan fuse state.

Value	Description	Alarm
0x00	Read only	
0x01	Fuse state - working	
0x02	Fuse state - blown	**ALARM**

Address	Parameter	Description
0x11	GasAlarmState	Robur alarm (gas/flame). Read from clamp no.6 (connection terminal inside Robur heater).

Value	Name	Description	Alarm
0x01	ON	Alarm detected	**ALARM**
0x02	OFF	No alarm	

Address	Parameter	Description
0x12	STBAlarmState	Air extraction temperature alarm (STB).

Value	Name	Description	Alarm
0x00	NC	PT1000 sensor not connected	**ALARM**
0x01	ON	STB alarm detected (T3 >= T_STB_REF))	**ALARM**
0x02	OFF	STB alarm not detected (T3 <= (T_STB_REF – 1 [K]))	

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   www.flowair.com

T-BOX Zone Modbus RTU V4.7.docx
48

Address	Parameter	Description		
0x13	FilterWorkTime	Filter work time. FilterWorkTime = 5 * FilterWorkTime (min)		

Value	Work time (min)	Description
0	0	Minimal value
65535	5*65535	Maximal Value

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

49

2.9.2. HOLDING REGISTER DRV R KM

Address	Parameter	Description
0x00	WorkMode	Work mode.
0x01	DamperForceMode	Damper forcing mode.
0x02	DamperForceTempRef	Target temperature value to open damper in forcing mode. (work mode *DamperForceMode == DAMPER_FMD_ ON*).
0x03	DamperForceLevelRef	Target temperature value to open damper. (work mode DamperMode == DAMPER_FMD_ ON) *Condition: Temp < DamperForceTempRef*
0x04	DamperLevelRef	Damper position.

0x00 WorkMode — Work mode.

Value	Work state	Description
0x00	NS	Read only
0x01	OFF	Device off
0x02	HEAT_AUTO	Automatic heating mode
0x03	HEAT_MANUAL	Manual heating mode
0x04	VENT	Ventilation mode

0x01 DamperForceMode — Damper forcing mode.

Value	Name	Description
0x00	DAMPER_FMD_NS	Read only
0x01	DAMPER_FMD_OFF	Forcing mode off
0x02	DAMPER_FMD_ ON	Depends on air draw temperature: *if (T1 < DamperForceTempRef) { DamperLevelRef = DamperForceRef; }*

0x02 DamperForceTempRef

Value	Temperature [K]	Description
−100	−10,0	Minimal value
150	15,0	Maximal value

0x03 DamperForceLevelRef

Value [%]	Description
0	**Minimal value**
100	Maximal value

0x04 DamperLevelRef

Value [%]	Description
0	Minimal value
100	**Maximal value**

Address	Parameter	Description
0x05	DamperContLevelRef	Damper position when: WorkMode == WM_WINTER_CONT.

Value[%]	Description
0	Minimal value
30	**Default value**
100	Maximal value

Address	Parameter	Description
0x06	FanRoofForceEffRef	Forcing fan roof ventilator speed (efficiency will be increased by *FanRoofForceEffRef*).

Value[%]	Description
-100	Minimal value
0	**Default value**
100	Maximal value

Address	Parameter	Description
0x07	FanRoofMode	Fan roof work mode.

Value	Name	Description
0x00	FR_MD_ NS	Ready only
0x01	**FR_MD_01**	**Depends on damper position (DamperLevelRef) and fan efficiency settings (FanEffRef)**
0x02	FR_MD_02	Depends on damper position (DamperLevelRef)

Address	Parameter	Description
008	STBTemperatureAlarm On	Target temperature to invoke STB alarm state *(Inpur Register 0x12)*. If > T3 alarm occurs. Default value ensures error occurrence before real STB Robur alarm (which needs manual reset from heater control box).

Value	Temperature [K]	Description
810	81,0	Minimal value
900	**90,0**	**Default value**
1200	120,0	Maximal value

Address	Parameter	Description
0x09	STBTemperatureAlarm Off	Target temperature to reset STB alarm state *(Inpur Register 0x12)*. If > T3 alarm occurs.

Value	Temperature [K]	Description
610	61,0	Minimal value
800	**80,0**	**Maximal value**

Additional condition:

STB_T_OFF < STB_T_REF

Address	Parameter	Description
0x0A	ContinuosModeFan SpeedRef	Fan speed after attaining target temperature.

Value	Description
100	Fan on
0	Fan off

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☎ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

51

Address	Parameter	Description		
0x0B	Gas Burner Level Ref	Gas heater power in manual heating work mode.		
		Value		**Description**
		0x00		Read only
		0x01		Gas burner first step
		0x02		Gas burner second step
0x0C	ExternalInputTH1Damper LevelRef	Damper position for EXT TH1		
		Value[%]		**Description**
		0		Minimal value
		100		**Default value**
		100		Maximal value
		Step: 5		
0x0D	FilterMaxWorkTime	Time after which the filter alarm will activate..		
		Value[h]		**Description**
		100		Minimal value
		4000		**Default value**
		4000		Maximal value
		Step:100		
0x0E	ExternalInputTH2Damper LevelRef	Damper position for EXT TH2.		
		Value[%]		**Description**
		0		Minimal value
		100		**Default value**
		100		Maximal value
		Step: 5		

2.10. DRV KM (LEO KM – Fan Heater with Mixing Chamber)

2.10.1. INPUT REGISTER DRV KM

Address	Name	Description
0x01	Software_type	<table><tr><th>Parameter</th><th>Description</th><th>Value</th></tr><tr><td>KM</td><td>KM</td><td>769</td></tr></table>
0x02	Connection count	Register for internal use
0x03	Soft_ver	Register for internal use
0x04	T1	Temperature measured by T1 sensor (fresh air temperature). <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th><th>Alarm</th></tr><tr><td>–500</td><td>–50,0</td><td>Minimal value</td><td></td></tr><tr><td>1000</td><td>100,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>–</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>–</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>
0x05	T3	Temperature measured by T3 sensor (air after water heat exchanger). <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th><th>Alarm</th></tr><tr><td>–500</td><td>–50,0</td><td>Minimal value</td><td></td></tr><tr><td>1000</td><td>100,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>–</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>–</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>
0x06	T4	Temperature measured by T4 sensor (air before water heat exchanger). <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th><th>Alarm</th></tr><tr><td>–500</td><td>–50,0</td><td>Minimal value</td><td></td></tr><tr><td>1000</td><td>100,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>–</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>–</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>
0x07	T5	Temperature measured by T5 sensor (water exchanger temperature). <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th><th>Alarm</th></tr><tr><td>–500</td><td>–50,0</td><td>Minimal value</td><td></td></tr><tr><td>1000</td><td>100,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>–</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>–</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>
0x08	ExternalGasDetectTH1	External gas detector signal - first threshold. <table><tr><th>Value</th><th>Description</th><th>Alarm</th></tr><tr><td>0x00</td><td>Gas concentration below threshold</td><td></td></tr><tr><td>0x01</td><td>Gas concentration exceeds threshold</td><td>ALARM</td></tr></table>

Address	Name	Description		
0x09	ExternalGasDetectTH2	External gas detector signal - second threshold.		
		Value	**Description**	**Alarm**
		0x00	Gas concentration below threshold	
		0x01	Gas concentration exceeds threshold	**ALARM**
0x0A	ExternalGasDetect_val	Gas concentration value - 0-10V DC input (gas detector scaling information required).		
		Value	**Voltage**	**Description**
		0	0,0	Minimal value
		100	10,0	Maximal value
0x0B	FanRoof_TK	TK signal from fan roof.		
		Value	**Description**	**Alarm**
		0x01	Temperature below safe limit.	
		0x02	Temperature above safe limit.	**ALARM**
0x0C	FanEff	Fan efficiency.		
		EC Fan - speed variable in range 0 - 100%		
		Value	**Fan speed**	**Description**
		0	0%	Minimal value
		100	100%	Maximal value
		AC Fan - 3 steps.		
		Value	**Gear**	**Description**
		0	**FAN_SPEED0**	**Fan off**
		1..33	FAN_SPEED1	First step
		34..66	FAN_SPEED2	Second step
		67..100	FAN_SPEED3	Third step
0x0D	FanUvoEff	Roof fan efficiency.		
		Value	**Description**	
		0	Minimal value	
		100	Maximal value	
0x0E	DamperLevel	Damper position.		
		Value	**Description**	
		0	Minimal value	
		100	Maximal value	
0x0F	DamperForceState	Forcing state for damper in mode DamperForceMode == DAMPER_FMD_ON		
		Value	**Condition**	
		0x01	Temp >= DamperForceTempRef	
		0x02	Temp < DamperForceTempRef	

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☎ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx
54

Address	Name	Description					
0x10	AntiFreezeState	Information about antifreeze (8 bits for respected mode).					
			Value 15..8 bit	Value 7..0 bit	Antifreeze	Description	Alarm
			–	0x01	Warehouse	Normal work mode.	
			–	0x02	Warehouse	Antifreeze enabled (user parameters overwritten)	**ALARM**
			0x01	–	Water Exchanger	Normal work mode.	
			0x02	–	Water Exchanger	Antifreeze enabled (user parameters overwritten)	**ALARM**
0x11	FilterWorkTime	Filter work time. FilterWorkTime = 5 * FilterWorkTime (min)					
			Value	Work time (min)	Description		
			0	0	Minimal value		
			65535	5*65535	Maximal Value		
0x12	FilterPreasureSwitchState	Filter pressure state.					
			Value	Description	Alarm		
			0x00	Not connected			
			0x01	Connected - good condition			
			0x02	Connected - bad condition	**WARNING**		
0x13	FanEcConnect	Information about EC Fan connection.					
			Value	Description	Alarm		
			0x01	Not connected	**ALARM**		
			0x02	Connected			

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

55

Address	Name	Description
0x14	FuseState	Fuse state for EC/3V/Roof fans, information can be read from 4 bits.

Bits	Description
3..0	Roof fan
4..7	EC fan
8...11	3V fan

Value	Description	Alarm
0x00	Read only	
0x01	Fuse state - working	
0x02	Fuse state - blown	**ALARM**

Example:

Fuse state 3V fan: working (0x1)

Register value: 0x100

Fuse state 3V fan: blown (0x2)

Register value: 0x200

Address	Name	Description
0x15	ValveState	Valve state.

Value	Name	Description
0x00	VALVE_IDLE	Valve in stand by mode (for 3-way valves)
0x01	VALVE_OPEN	Opening valve
0x02	VALVE_CLOSE	Closing valve

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

56

2.10.2. HOLDING REGISTER DRV KM

Address	Name	Description
0x00	WorkMode	Work mode

Value	Work mode	Description
0	WM_NS	Read only
1	WM_OFF	Device off
2	WM_HT	Heat mode
3	WM_COOL	Cool mode
4	WM_VENT	Ventilation mode

Address	Name	Description
0x01	DamperForceMode	Damper forcing mode

Value	Work mode	Description
0	DAMPER_FMD_NS	Read only
1	DAMPER_FMD_OFF	Forcing mode off
2	DAMPER_FMD_ ON	Depends on air draw temperature: *if (T1 < DamperForceTempRef) { DamperLevelRef = DamperForceRef; }*

Address	Name	Description
0x02	DamperForceTempRef	Target temperature value to open damper in forcing mode. (work mode *DamperForceMode == DAMPER_FMD_ ON*).

Value	Temperature [C]	Description
–100	–10,0	Minimal value
150	15,0	Maximal value

Address	Name	Description
0x03	DamperForceLevelRef	Target temperature value to open damper. (work mode DamperMode == DAMPER_FMD_ ON) *Condition: Temp < DamperForceTempRef*

Value	Damper airflow regulation [%]	Description
0	0	Minimal value
100	100	Maximal value

Address	Name	Description
0x04	DamperLevelRef	Damper settings:

Value	Damper airflow regulation [%]	Description
0	0	Minimal value
100	100	Maximal value

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☐ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

57

Address	Name	Description
0x05	FanEffRef	Fan settings: *EC Fan - speed variable in range 0 - 100%* <table><tr><td>**Value**</td><td>**Fan speed**</td><td>**Description**</td></tr><tr><td>0</td><td>0%</td><td>Minimal value</td></tr><tr><td>100</td><td>100%</td><td>Maximal value</td></tr></table> *AC Fan - 3 steps.* <table><tr><td>**Value**</td><td>**Gear**</td><td>**Description**</td></tr><tr><td>**0**</td><td>**FAN_SPEED0**</td><td>**Fan off**</td></tr><tr><td>1..33</td><td>FAN_SPEED1</td><td>First step</td></tr><tr><td>34..66</td><td>FAN_SPEED2</td><td>Second step</td></tr><tr><td>67..100</td><td>FAN_SPEED3</td><td>Third step</td></tr></table>
0x06	FanRoofForceEffRef	Forcing fan roof efficiency (FanRoofForceEffRef will be added to FanEffRef). <table><tr><td>**Value**</td><td>**Fan efficiency**</td><td>**Description**</td></tr><tr><td>-100</td><td>-100</td><td>Minimal value</td></tr><tr><td>100</td><td>100</td><td>Maximal value</td></tr></table>
0x07	FanRoofMode	Fan roof work mode. <table><tr><td>**Value**</td><td>**Work mode**</td><td>**Description**</td></tr><tr><td>0</td><td>FR_MD_NS</td><td>Read only.</td></tr><tr><td>1</td><td>FR_MD_01</td><td>Fan roof efficiency depended on DamperLevelRef and FanEffRef.</td></tr><tr><td>2</td><td>FR_MD_02</td><td>Fan roof efficiency depended on DamperLevelRef.</td></tr></table>
0x08	ThermostatModeState	Thermostatic mode. <table><tr><td>**Value**</td><td>**Work mode**</td><td>**Description**</td></tr><tr><td>1</td><td>THERMO_MD_ON</td><td>Thermostatic mode on</td></tr><tr><td>2</td><td>THERMO_MD_OFF</td><td>Thermostatic mode off</td></tr></table>
0x09	ThermostatModeFanEffRef	Fan settings for thermostatic mode. *EC Fan - speed variable in range 0 - 100%* <table><tr><td>**Value**</td><td>**Fan speed**</td><td>**Description**</td></tr><tr><td>0</td><td>0%</td><td>Minimal value</td></tr><tr><td>100</td><td>100%</td><td>Maximal value</td></tr></table> *AC Fan - 3 steps.* <table><tr><td>**Value**</td><td>**Gear**</td><td>**Description**</td></tr><tr><td>**0**</td><td>**FAN_SPEED0**</td><td>**Fan off**</td></tr><tr><td>1..33</td><td>FAN_SPEED1</td><td>First step</td></tr><tr><td>34..66</td><td>FAN_SPEED2</td><td>Second step</td></tr><tr><td>67..100</td><td>FAN_SPEED3</td><td>Third step</td></tr></table>

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

58

Address	Name	Description		
0x0A	TLeasSensorSelectSupply	Leading sensor select		
		Value	**Work mode**	**Description**
		0	TLST_ZONE	Zone sensor
		2	TLST_T3	Read only
0x0B	T3LeadSensorOffset	Temperature sensor offset		
		Value	**Fan speed**	**Description**
		–100	–10,0	Minimal value
		100	10,0	Maximal value
		Step; 5 **Multiplier: 0,1**		
0x0C	FilterMaxWorkTime	Time after which the filter alarm will activate		
		Value[h]	**Description**	
		100	Minimal value	
		4000	**Default value**	
		4000	Maximal value	
		Step:100		
0x0D	ExternalInputTH1FanRef	Fan efficiency for for EXT TH1		
		Value[%]	**Description**	
		0	Minimal value	
		100	**Default value**	
		100	Maximal value	
0x0E	ExternalInputTH2FanRef	Fan efficiency for EXT TH2		
		Value[%]	**Description**	
		0	Minimal value	
		100	**Default value**	
		100	Maximal value	
0x0F	ExternalInputTH1Damper LevelRef	Damper position for EXT TH1		
		Value[%]	**Description**	
		0	Minimal value	
		100	**Default value**	
		100	Maximal value	
		Step: 5		
0x10	External Input TH2 Damper LevelRef	Damper position for EXT TH2		
		Value[%]	**Description**	
		0	Minimal value	
		100	**Default value**	
		100	Maximal value	
		Step: 5		

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

59

2.11. DRV OXEN (OXEN – Heat Recovery Unit)

2.11.1. INPUT REGISTER DRV OXEN

Address	Name	Description
0x00	Staus1	Status register no 1.

Status1 detail:

BIT	Name	Description
0…3	WorkMode	Oxen work mode.

Value	Name	Description
0x00	NONE	Type not identified
0x01	COLD	Cold OXEN
0x02	ELECTRIC	Electric OXEN
0x03	HOT	Water OXEN

BIT	Name	Description
4…5	OxenType	Oxen Type.

Value	Name	Description	Alarm
0x00	OFF	Normal work mode	
0x01	ON	Antifreeze enabled (user parameters overwritten)	**ALARM**

BIT	Name	Description
6…7	AfWaterEx	Water exchanger antifreeze information.

Value	Name	Description	Alarm
0x00	OFF	Normal work mode	
0x01	ON	Antifreeze enabled (user parameters overwritten)	**ALARM**

BIT	Name	Description
8…9	AfHeatCrossEx	Heat cross exchanger antifreeze information.

Value	Name	Description
0x00	IDLE	Initial value after supplying voltage
0x01	INIT	Oxen initialization
0x02	READY	Oxen ready

BIT	Name	Description
10..15	-	Not used

Address	Name	Description
0x01	Status2	Not used.
0x02	T1	Temperature measured by T1 sensor (fresh air temperature).

Value	Temperature [C]	Description	Alarm
-500	-50,0	Minimal value	
1000	100,0	Maximal value	
0x7000	-	Short circuit	
0x7FFF		PT1000 sensor not connected	**ALARM**

Address	Name	Description				
0x03	T2	Temperature measured by T2 sensor (air near fan extraction).				
		Value	**Temperature [C]**	**Description**	**Alarm**	
		–500	–50,0	Minimal value		
		1000	100,0	Maximal value		
		0x7000	–	Short circuit		
		0x7FFF	–	PT1000 sensor not connected	**ALARM**	
0x04	T3	Temperature measured by T3 sensor (air after water heat exchanger).				
		Value	**Temperature [C]**	**Description**	**Alarm**	
		–500	–50,0	Minimal value		
		1000	100,0	Maximal value		
		0x7000	–	Short circuit		
		0x7FFF	–	PT1000 sensor not connected	**ALARM**	
0x05	T4	Temperature measured by T4 sensor (room air / air return sensor).				
		Value	**Temperature [C]**	**Description**	**Alarm**	
		–500	–50,0	Minimal value		
		1000	100,0	Maximal value		
		0x7000	–	Short circuit		
		0x7FFF	–	PT1000 sensor not connected	**ALARM**	
0x06	T5	Temperature measured by T5 sensor (water exchanger temperature).				
		Value	**Temperature [C]**	**Description**	**Alarm**	
		–500	–50,0	Minimal value		
		1000	100,0	Maximal value		
		0x7000	–	Short circuit		
		0x7FFF	–	PT1000 sensor not connected	**ALARM**	

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

61

Address	Name	Description
0x07	Outputs	Outputs status.

BIT	Name	Description		
0	Damper	Damper status.		
		Value		Description
		0x00		Closed
		0x01		Opened
1	Bypass	Bypass status.		
		Value		Description
		0x00		Closed
		0x01		Opened
2…3	Valve	Valve status.		
		Value	Name	Description
		0x00	IDLE	IDLE state (3-way valve)
		0x01	OPEN	Opening valve
		0x02	CLOSE	Closing valve
4…15	-	Not used		

Address	Name	Description
0x08	Inputs	Inputs status.

BIT	Name	Description
0	NP_IN1	Non-potential input state IN1
1	NP_IN2	Non-potential input state IN2
2	NP_IN3	Non-potential input state IN3
3	SW1_P5	SW1 switch state, position 5
4	SW1_P4	SW1 switch state, position 4
5	SW1_P3	SW1 switch state, position 3
6	SW1_P2	SW1 switch state, position 2
7	SW1_P1	SW1 switch state, position 1

Non-potential inputs state:

Value	Name	Description
0	CLOSE	Short circuit
1	OPEN	Open

Switch states:

Value	Name	Description
0	OFF	Switch in OFF position
1	ON	Switch in ON position

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   www.flowair.com

T-BOX Zone Modbus RTU V4.7.docx

62

Address	Name	Description
0x09	FilterWorkTime	Filter work time.

Value	[min]	Description
0	5 * 0	Minimal value
65534	5 * 65534	Maximal value

Address	Name	Description
0x0A	FansEff_1	Fan efficiency in group I (supply fans).
		EC Fan - speed variable in range 0 - 100%

Value	Fan speed	Description
0	0%	Minimal value
100	100%	Maximal value

Address	Name	Description
0x0B	FansEff_2	Fan efficiency setting in group II (exhaust fans).
		EC Fan - speed variable in range 0 - 100%

Value	Fan speed	Description
0	0%	Minimal value
100	100%	Maximal value

Address	Name	Description
0x0C	OxenElectric_PtcPower	Not used.
0x0D	OxenElectric_PtcTk	Not used

T-BOX Zone Modbus RTU V4.7.docx
63

2.11.2. HOLDING REGISTER DRV OXEN

Address	Name	Description
0x00	FansEffRef_1	Fan efficiency setting in group I. *EC Fan - speed variable in range 0 - 100%* | Value	Fan speed	Description | |---|---|---| | 0 | 0% | Minimal value | | 100 | 100% | Maximal value | Note: FansEffRef_1 = FansEffRef_2
0x01	FansEffRef_2	Fan efficiency setting in group II. *EC Fan - speed variable in range 0 - 100%* | Value	Fan speed	Description | |---|---|---| | 0 | 0% | Minimal value | | 100 | 100% | Maximal value |
0x02	OxenState	Work status. | Value	Work status	Description | |---|---|---| | 0 | OXEN_ST_OFF | Disabled | | 1 | OXEN_ST_ECO | Enabled |
0x03	OxenMode	Work mode (bypass). | Value	Work status	Description | |---|---|---| | 0 | OXEN_MD_AUTO | Automatic adjustment (automatic adjustment) | | 1 | OXEN_MD_WINTER | Winter adjustment (bypass off) | | 2 | OXEN_MD_SUMMER | Summer adjustment (bypass on) |
0x04	FilterMaxWorkTime	Time after which the filter alarm will activate | Value[h]	Description | |---|---| | 100 | Minimal value | | 4000 | **Default value** | | 4000 | Maximal value | **Step:100**
0x05	TleadSensorSelectSupply	Leading sensor offset. | Value	Work status	Description | |---|---|---| | 0 | TLST_ZONE | Zone sensor | | 2 | TLST_T3 | Read only |
0x06	T3LeadSensorOff	Temperature sensor offset | Value	Fan speed	Description | |---|---|---| | –100 | 0% | Minimal value | | 100 | 100% | Maximal value | **Step:5** **Multiplier: 0,1**

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

64

Address	Name	Description
0x07	ExternalInputTH1FanRef1	An efficiency setting in group I (supply fans) For EXT TH1

Value	Fan speed	Description
0	0%	Minimal value
100	100%	Maximal value

Default value: 100

Address	Name	Description
0x08	ExternalInputTH2FanRef1	An efficiency setting in group I (supply fans) For EXT TH2

Value	Fan speed	Description
0	0%	Minimal value
100	100%	Maximal value

Default value: 100

Address	Name	Description
0x09	ExternalInputTH1FanRef2	An efficiency setting in group II (exhaust fans) For EXT TH1

Value	Fan speed	Description
0	0%	Minimal value
100	100%	Maximal value

Address	Name	Description
0x0A	ExternalInputTH2FanRef2	An efficiency setting in group II (exhaust fans) For EXT TH2

Value	Fan speed	Description
0	0%	Minimal value
100	100%	Maximal value

Address	Name	Description
0x09	RegParam_T	Doubling time for adjustment (regulator) (OXEN HOT).

Value	Description
0	Minimal value
1000	Maximal value

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

65

2.12. DRV CUBE (CUBE – Rooftop Unit)

2.12.1. INPUT REGISTER DRV CUBE

Address	Name	Description		
0x09	ambient_temp_value	Outside temperature.		
		Value	**Temperature [C]**	**Description**
		−640	−64,0	Minimal value
		640	64,0	Maximal value
0x0A	supply_temp_value	Supply air temperature.		
		Value	**Temperature [C]**	**Description**
		−640	−64,0	Minimal value
		640	64,0	Maximal value
0x0B	return_temp_value	Exhaust air temperature.		
		Value	**Temperature [C]**	**Description**
		−640	−64,0	Minimal value
		640	64,0	Maximal value
0x0C	water_temp_value	Water exchanger temperature.		
		Value	**Temperature [C]**	**Description**
		−640	−64,0	Minimal value
		1500	150,0	Maximal value
0x0D	TempRoom_ADD	Room Sensor.		
		Value	**Temperature [C]**	**Description**
		−640	−64,0	Minimal value
		1500	150,0	Maximal value
0x0E	recirculation_damper_level	Recirculation damper level.		
		Value	**Description**	
		0	Minimal value	
		100	Maximal value	
0x0F	swirl_diffuser_position	Swirl diffuser position.		
		Value	**Description**	
		0	Minimal value	
		100	Maximal value	
0x10	NULL	Not used.		
0x10	rotary_level	Rotor level.		
		Value	**Description**	
		0	Minimal value	
		100	Maximal value	

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📞 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

66

Address	Name	Description		
0x11	fan_supply_flow	Fan supply flow.		
		Value	**Description**	
		0	Minimal value	
		10000	Maximal value	
0x12	gas_heating_value	Gas heating value.		
		Value	**Description**	
		0	Minimal value	
		100	Maximal value	
0x13	CO2_status	Status CO2 Description is split between <MSB> <LSB>. <MSB> ignored <LSB> CO2 status		

		Value	**Name**	**Description**	**Alarm**
		0x00	CO2_STAT_OK	CO2 status OK	
		0x01	CO2_STAT_L1	CO2 level 1	**ALARM**
		0x02	CO2_STAT_L2	CO2 level 2	**ALARM**

0x14	Rooftop_work_mode	Rooftop work mode Description is split between <MSB> <LSB>. <MSB> ignored <LSB> Work mode

		Value	**Work status**	**Description**
		1	RT_WM_VENT	Ventilation
		2	RT_WM_HTG	Heating
		3	RT_WM_HTGREC	Heating with recovery
		4	RT_WM_CLG	Cooling
		5	RT_WM_CLGREC	Cooling with recovery

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

67

Address	Name	Description
0x15	Rooftop_current_work _mode	Rooftop current work mode Description is split between <MSB> <LSB>. <MSB> ignored <LSB> Current work mode
0x16	Alarm	**Alarm** Description is split between <MSB> <LSB>. <MSB> ignored <LSB> Alarms
0x17	room_temp_sensor_status	Room temp sensor status.
0x18	NULL	Not used.
0x19	NULL	Not used.
0x1A	ControlSource	

Table for 0x15:

Value	Work status	Description
1	WM_STOP	Stop
2	WM_FREEZ	Freez
3	WM_OFF	Off
4	WM_STARTUP	StrtUp
5	WM_ECO	Eco
6	WM_CMFRT	Cmfrt
7	WM_CO2	CO2
8	WM_THMST	Thmst
9	WM_NGHTCLG	NghtClg
10	WM_OVRRUN	OvrRun
11	WM_DEFROST	DeFrost

Table for 0x16:

Value	Work status	Description
0	AL_OK	OK
1	AL_MAINTENANCE	Maintenance
2	AL_WARNING	Warning
3	AL_FAULT	Fault
4	AL_DANGER	Danger

Table for 0x17:

Value	Description
0	OK
1	no sensor
X5	Short circuit

Table for 0x1A:

Value	Work status	Description
1	LOCAL	Rooftop HMI
2	SCHEDULE	Calendar from Rooftop
3	TBOX	T-box as controller
4	BMS	External Modbus

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

68

2.12.2. HOLDING REGISTER DRV CUBE

Address	Name	Description
0x00	WorkMode	Work mode settings Description is split between <MSB> <LSB>. <MSB> ignored <LSB> Work mode | Value	Work status	Description | |---|---|---| | 1 | WM_OFF | Device off | | 2 | WM_ON | Device on | | 3 | WM_THERM | Device Therm |
0x01	fan_eff	Fan efficiency setting - variable in range 0 - 100% | Value	Fan efficiency	Description | |---|---|---| | 0 | 0% | Minimal value | | 100 | 100% | Maximal value |
0x02	fan_eff_CO2_I	Fan efficiency settings for CO2 sensor stage 1 - variable in range 0 - 100% | Value	Fan efficiency	Description | |---|---|---| | 0 | 0% | Minimal value | | 100 | 100% | Maximal value |
0x03	fan_eff_CO2_II	Fan efficiency settings for CO2 sensor stage 2 - variable in range 0 - 100% | Value	Fan efficiency	Description | |---|---|---| | 0 | 0% | Minimal value | | 100 | 100% | Maximal value |
0x04	recirculation_mode	Recirculation mode settings Description is split between <MSB> <LSB>. <MSB> ignored <LSB> Recirculation mode | Value	Recirculation Mode	Description | |---|---|---| | 0 | RM_AUTO | Auto mode | | 1 | RM_MANUAL | Manual mode |
0x05	recirculation_value	Recirculation value - variable in range 0 - 100% | Value	Recirculation value	Description | |---|---|---| | 0 | 0% | Minimal value | | 100 | 100% | Maximal value |
0x06	recirculation_value_CO2_I	Recirculation value for CO2 sensor stage 1 - variable in range 0 - 100% | Value	Recirculation value	Description | |---|---|---| | 0 | 0% | Minimal value | | 100 | 100% | Maximal value |

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   www.flowair.com

T-BOX Zone Modbus RTU V4.7.docx

70

Address	Name	Description
0x07	recirculation_value_CO2_II	Recirculation value for CO2 sensor stage 2 - variable in range 0 - 100%

Value	Recirculation value	Description
0	0%	Minimal value
100	100%	Maximal value

Address	Name	Description
0x08	work_mode_NW	Work mode NW (swirl diffuser)
		Description is split between <MSB> <LSB>.
		<MSB> ignored
		<LSB> Work mode NW

Value	Work Mode	Description
0	WM_NW_AUTO	Auto mode
1	WM_NW_MANUAL	Manual mode

Address	Name	Description
0x09	swirl_diffuser_level	Swirl diffuser level.

Value	Swirl diff. level	Description
30	30%	Minimal value
100	100%	Maximal value

Address	Name	Description
0x0A	Clg_swirl_diffuser_level	Swirl diffuser level in cooling mode.

Value	Swirl diff. level	Description
30	30%	Minimal value
100	100%	Maximal value

Address	Name	Description
0x0B	Htg_swirl_diffuser_level	Swirl diffuser level in heating mode.

Value	Swirl diff. level	Description
30	30%	Minimal value
100	100%	Maximal value

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📞 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

71

2.13. DRV AX (ELIS AX – Air Curtain)

2.13.1. INPUT REGISTER DRV AX

Address	Name	Description
0x01	Software_type	<table><tr><th>Parameter</th><th>Description</th><th>Value</th></tr><tr><td>DRV_ELIS_EC</td><td>DRV ELIS EC</td><td>6146</td></tr></table>
0x02	Connection count	Register for internal use.
0x03	Soft_ver	Register for internal use.
0x04	T1	Temperature value from the sensor connected to the PT1 input - outdoor air temperature measurement. <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th><th>Alarm</th></tr><tr><td>-1500</td><td>-150,0</td><td>Minimal value</td><td></td></tr><tr><td>2000</td><td>200,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>
0x05	T3	Temperature value from sensor connected to PT3 input - supply air temperature measurement. <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th><th>Alarm</th></tr><tr><td>-1500</td><td>-150,0</td><td>Minimal value</td><td></td></tr><tr><td>2000</td><td>200,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>
0x06	T4	Temperature measured by T4 sensor (room temperature). <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th><th>Alarm</th></tr><tr><td>-1500</td><td>-150,0</td><td>Minimal value</td><td></td></tr><tr><td>2000</td><td>200,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>
0x07	T5	Temperature value from the sensor connected to the input. PT5 - measurement of the temperature of water on the post-return pipe of the water exchanger. <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th><th>Alarm</th></tr><tr><td>-1500</td><td>-150,0</td><td>Minimal value</td><td></td></tr><tr><td>2000</td><td>200,0</td><td>Maximal value</td><td></td></tr><tr><td>0x7000</td><td>-</td><td>Short circuit</td><td></td></tr><tr><td>0x7FFF</td><td>-</td><td>PT1000 sensor not connected</td><td>ALARM</td></tr></table>

Address	Name	Description
0x08	CurtainState1	The register contains information on what state the controller is in. Each bit of the register represents whether a particular function of the controller has been activated. The concept of function is understood here in a broad sense, i.e. it can represent the operating mode of the curtain (in Holding Regirters register: *Elis_Work_Mode*) or the currently running program (in Holding Regirters register: *Program*).

BIT	Name	Description for BIT == 1
0	WM_OFF	The controller is in OFF state
1	WM_VENT	The controller is in VENT state
2	WM_HEAT	The controller is in HEAT state
3	WM_SMART	The controller is in SMART state
4	PROGRAM_K1	K1 program is being implemented
5	PROGRAM_K2	K2 program is being implemented
6	PROGRAM_K3	K3 program is being implemented
7	ADD_HEAT	Condition of the reheating function has been met
8	STANDBY	Condition of the standby function has been met
9	PREHEAT	Condition of the preheating function has been fulfilled
10	AF_WAREHOUSE	Condition of antifreeze protection of the hall has occurred
11	AF_WATER_EXCHANGER	Condition of protection of the water exchanger has occurred
12	DOOR_OPEN_FREQ	Condition of the door frequency detection function has occurred
13	Curtain_State_02	Curtain_State_02 register value > 0
14	Curtain_State_03	Curtain_State_03 register value > 0
15	NOT_USE	Not used (value 0x0)

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx
73

Address	Name	Description			
0x09	CurtainState2	Controller status register extensions.			

BIT	Name	Description for BIT == 1	Alarm
0	WM_OFF	The controller is in OFF state	**ALARM**
1	WM_VENT	The controller is in VENT state	**ALARM**
2	WM_HEAT	The controller is in HEAT state	**ALARM**
3	WM_SMART	The controller is in SMART state	**ALARM**
4	PROGRAM_K1	K1 program is being implemented	**ALARM**
5	PROGRAM_K2	K2 program is being implemented	**ALARM**
6	PROGRAM_K3	K3 program is being implemented	**ALARM**
7	ADD_HEAT	Condition of the reheating function has been met	**ALARM**
8	STANDBY	Condition of the standby function has been met	**ALARM**
9	PREHEAT	Condition of the preheating function has been fulfilled	**ALARM**
10	AF_WAREHOUSE	Condition of antifreeze protection of the hall has occurred	**ALARM**
11	AF_WATER_EXCHANGER	Condition of protection of the water exchanger has occurred	
12	DOOR_OPEN_FREQ	Condition of the door frequency detection function has occurred	
13	Curtain_State_02	Curtain_State_02 register value > 0	
14	Curtain_State_03	Curtain_State_03 register value > 0	
15	NOT_USE	Not used (value 0x0)	

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☎ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx
74

Address	Name	Description
0x0A	CurtainState3	Controller status register extensions.

BIT	Name	Description for BIT == 1	Alarm
0	FUSE_FAN1	Blown fuse for FAN1	**ALARM**
1	FUSE_FAN2	Blown fuse for FAN2	**ALARM**
2	FUSE_RELAY	Blown fuse for RELAY	**ALARM**
3	OUT1_WORK	Information on the state of WORK (output open)	
4	OUT2_EMERGENCY	State information of EMERGENCY (output open)	**ALARM**
5	PREHEAT_T5_REF_FORCE	Information about forcing by register [0x0C] EWM_HEAT_T5_Max	
6	NOT_USE	Not used (value 0x0)	
7	NOT_USE	Not used (value 0x0)	
8	NOT_USE	Not used (value 0x0)	
9	NOT_USE	Not used (value 0x0)	
10	NOT_USE	Not used (value 0x0)	
11	NOT_USE	Not used (value 0x0)	
12	NOT_USE	Not used (value 0x0)	
13	NOT_USE	Not used (value 0x0)	
14	NOT_USE	Not used (value 0x0)	
15	NOT_USE	Not used (value 0x0)	

Address	Name	Description
0x0B... ...0x11	Fan1Speed...Fan7Speed	Actual value of the supply air fan speed. Fan speed value read from input FAN_EC_1 ... FAN_EC_7

Value	Description
0	Minimum value
5000	Maximum value

Address	Name	Description
0x12	FilterWorkTime	Filter operating time.

Value	Filter operating time [min]	Description
0	0	Minimum value
65535	5*65535	Maximum value

*FilterWorkTime = 5 * FilterWorkTime [min]*

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📞 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

75

Address	Name	Description
0x13	ValveRealysState	Current status of the valve connected to *VALVE_RELAYS*.

Current status of the valve connected to *VALVE_RELAYS*.

Value	Name	L1	L2	Description
0x00	IDLE	0	0	Valve at rest (condition for three-point valve)
0x01	OPEN	0	1	Opening the valve
0x02	CLOSE	1	0	Closing the valve
-	-	1	1	Unauthorized condition

L1, L2 contacts:

0 - opened

1 - closed

Address	Name	Description
0x14	Valve0-10State	The current status of the valve connected to *0-10 V.*

The current status of the valve connected to *0-10 V.*

Value read from input 0-10V

Value [%]	[V]	Description
0	0,0	Minimum value
100	10,0	Maximum value

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

76

2.13.2. HOLDING REGISTER DRV AX

Address	Name	Description
0x00	WorkMode,	Work mode. | Value	Work status	Description
-------	-------------	-------------
0x01	OFF	Device off
0x02	HEAT	Operation mode: heating
0x03	VENT	Operation mode: ventilation
0x04	SMART	Operation mode: smart	
0x01	FanWorkMode	Fan mode: | Value	Name	Description
-------	------	-------------
0x01	MANUAL	Fan work in manual mode
0x02	AUTO	Fan work in auto mode. | **Default value: MANUAL (0x01)**
0x02	Program	The program according to which the curtain works: | Value	Name	Description
-------	------	-------------
0x01	K1	K1 program has been selected. (Temp. Drop or Door Switch Turns On Unit)
0x02	K2	K2 program has been selected. (Door Switch Turns On unit, Than temp. Drop Turns On Heating)
0x03	K3	K3 program has been selected. (Temp. Drop Turns On Unit, No reaction for Door Switch) | **Default value: K1 (0x01)**
0x03	FWM_ManualHeatVentRef	Fan efficiency: $(Fan\_Work\_Mode == \text{MANUAL}) \&\& (Elis\_Work\_Mode == (\text{HEAT or VENT}))$ | Value	Efficeincy [%]	Description
-------	----------------	-------------
0	0	Minimum value
100	100	Maximum value | **Default value: 50 [%]**
0x04	FWM_StandbyRef	Standard fan performance set point (STANDBY). Parameter active if: $(Fan\_Work\_Mode == \text{MANUAL}) \| (Fan\_Work\_Mode == \text{AUTO})$ | Value	Efficeincy [%]	Description
-------	----------------	-------------
0	0	Minimum value
100	100	Maximum value | **Default value: 20 [%]**

Address	Name	Description
0x05	FWM_AutoHeatVentMin	The maximum value of the fan capacity in the automatic operating state. Parameter active if: (*Fan_Work_Mode* == AUTO) && (*Elis_Work_Mode* == (HEAT || VENT)) <table><tr><th>Value</th><th>Efficeincy [%]</th><th>Description</th></tr><tr><td>0</td><td>0</td><td>Minimum value</td></tr><tr><td>100</td><td>100</td><td>Maximum value</td></tr></table> **Default value: 0 [%]** Condition: *FWM_Auto_Heat_Vent_Min* < *FWM_Auto_Heat_Vent_Max*
0x06	FWM_AutoHeatVentMax	The maximum value of the fan capacity in the automatic operating state. Parameter active if: (*Fan_Work_Mode* == AUTO) && (*Elis_Work_Mode* == (HEAT || VENT)) <table><tr><th>Value</th><th>Efficeincy [%]</th><th>Description</th></tr><tr><td>0</td><td>0</td><td>Minimum value</td></tr><tr><td>100</td><td>100</td><td>Maximum value</td></tr></table> **Default value: 100 [%]** Condition: *FWM_Auto_Heat_Vent_Max* > *FWM_Auto_Heat_Vent_Min*
0x07	EWM_HeatT3Ref	Temperature setpoint for supply air for heating (HEAT). <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th></tr><tr><td>250</td><td>25</td><td>Minimum value</td></tr><tr><td>450</td><td>45</td><td>Maximum value</td></tr></table> **Default value: 32,0 [C] (320)**
0x08	EWM_HeatT5Max	Return water temperature limitation value for heating (HEAT). <table><tr><th>Value</th><th>Temperature [C]</th><th>Description</th></tr><tr><td>200</td><td>20</td><td>Minimum value</td></tr><tr><td>500</td><td>50</td><td>Maximum value</td></tr></table> **Default value: 32,0 [C] (320)**
0x09	EWM_HeatT5LimitMode	Enable / disable return water temperature limitation for heating (HEAT). <table><tr><th>Value</th><th>Name</th><th>Description</th></tr><tr><td>0x01</td><td>ON</td><td>Enable</td></tr><tr><td>0x02</td><td>OFF</td><td>Disable</td></tr></table> **Default value: OFF (0x02)**

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

78

Address	Name	Description
0x0A	PrheatT5Ref	Return water temperature limitation value for heating (HEAT).

Value	Temperature [C]	Description
200	20	Minimum value
600	60	Maximum value

Default value: 30,0 [C] (300)

(*) Value Preheat_T5_Ref depends on the value of the parameter *WM_HEAT_T5_Max*.

If:

$EMW\_HEAT\_T5\_Limit\_Mode\_On\_Off == ON$,

and:

$Preheat\_T5\_Ref > EWM\_HEAT\_T5\_Max$,

than the return water temperature control algorithm will take the value from the register *[0x0C] EWM_HEAT_T5_Max*. In addition, in the register *[0x0A] Curtain_State_03* it is possible to read the information on the *PREHEAT_T5_REF_FORCE* field about the forcing of *Preheat_T5_Ref* through the *[0x0C] EWM_HEAT_T5_Max register*.

Address	Name	Description
0x0B	StanbyFanIdleDelay	Delay time of standby fan operation (STANDBY)

Value	Description
0	Minimum delay in [s] (standby deactivation)
65534	Maximum delay in [s]
0xFFFF	Continuous operation

Defaulkt value: 300 s

For:

$Standby\_Fan\_Idle\_Delay > 0$,

The condition must be met:

$Standby\_Fan\_Idle\_Delay >= Standby\_Valve\_Idle\_Delay$.

If:

$Standby\_Fan\_Idle\_Delay < Standby\_Valve\_Idle\_Delay$

then to register:

[0x14] Standby_Valve_Idle_Delay

will be written the value of:

[0x13] Standby_Fan_Idle_Delay.

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

79

Address	Name	Description
0x0C	StanbyValveIdleDelay	Delay time of valve operation in standby (STANDBY)

Value	Description
0	Minimum delay in [s] (standby deactivation)
65534	Maximum delay in [s]
0xFFFF	Continuous operation

Default value: 300 s

For:

$$Standby\_Valve\_Idle\_Delay > 0,$$

The condition must be met:

$$Standby\_Valve\_Idle\_Delay <= Standby\_Fan\_Idle\_Delay.$$

If:

$$Standby\_Valve\_Idle\_Delay > Standby\_Fan\_Idle\_Delay$$

then to register:

[0x13] Standby_Fan_Idle_Delay

will be written the value of:

[0x14] Standby_Valve_Idle_Delay.

Address	Name	Description
0x0D	AntifreezeWareHouseOn	Enable / disable return water temperature limitation for heating (HEAT).

Value	Name	Description
0x01	ON	Enable
0x02	OFF	Disable

Default value: OFF (0x02)

Address	Name	Description
0x0E	AntifreezeWareTempOn	Antifreeze warehouse threshold.

Value	Name	Description
50	5,0	Minimum value
150	15,0	Maximum value

Default value: 7,0 [C]

Address	Name	Description
0x0F	AntifreezeWaterExchangeOn	Water exchanger antifreeze activation.

Value	Name	Description
0x01	ON	Enable
0x02	OFF	Disable

Default value: ON (0x01)

Address	Name	Description
0x10	AntifreezeWaterExchangeT3	Threshold value of supply air temperature for the condition of activation of anti-freeze protection of water exchanger.

Value	Temperature [C]	Description
50	5,0	Minimum value
100	10,0	Maximum value

Default value: 7,0 [C] (70)

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☎ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

80

Address	Name	Description
0x11	AntifreezeWaterExchangeT5	The threshold value of the return water temperature for the condition of tripping the anti-freeze protection of the water exchanger.

Value	Temperature [C]	Description
50	5,0	Minimum value
200	20,0	Maximum value

Default value: 7,0 [C] (70)

Address	Name	Description
0x12	PreheatOnOff	Enable / disable preheating (PREHAET)

Value	Name	Description
0x01	ON	Enable
0x02	OFF	Disable

Default value: OFF (0x02)

Address	Name	Description
0x13	FilterMaxWorkTime	Erasing the filter operating time counter

Value	Name	Description
0x00	NS	Enable
0x01	RESET	Disable

Default value: OFF (0x02)

Address	Name	Description
0x14	DoorOpenFreqAlpha Threshold	Detection threshold value of door opening frequency in the mode. Parameter active if:

Elis_Work_Mode == SMART

Value	Name	Description
0x00	NS	Enable
0x01	RESET	Disable

Default value: 0,60 (60)

Address	Name	Description
0x15	DoorOpenFreqTimePeriod	Setpoint of the detection period of the door opening frequency. Parameter active if :

Elis_Work_Mode == SMART

Value [s]	Description
2*60	Minimum value
15*60	Maximum value

Default value: 5*60 [s]

Address	Name	Description
0x16	FWMAutoAddHeatMin	Minimum value of fan capacity in reheating (ADD HEAT). Parameter active if:

Fan_Work_Mode == AUTO

Value [%]	Description
0	Minimum value
100	Maximum value

Default value: 5%

Condition: *FWM_Auto_Add_Heat_Min < FWM_Auto_Add_Heat_Max*

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☐ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

81

Address	Name	Description
0x17	FWMAutoAddHeatMax	Maximumvalue of fan capacity in reheating (ADD HEAT). Parameter active if: *Fan_Work_Mode == AUTO*
0x18	EWMSmartT124h	Temperature setpoint for determining transition condition between modes VENT - > HEAT. Parameter active if: *Elis_Work_Mode == SMART*
0x19	EWMSmartT13h	Temperature setpoint for determining transition condition between modes HEAT- > VENT. Parameter active if: *Elis_Work_Mode == SMART*
0x1A	HeatT3_PI_KP	KP gain value of the PI controller for the supply air temperature control system (T3).
0x1B	HeatT3_PI_TI	The value of the doubling time TI of the PI controller for the supply air temperature control system (T3).

0x17 — FWMAutoAddHeatMax

Value [%]	Description
0	Minimum value
100	Maximum value

Default value: 5%

Condition: *FWM_Auto_Add_Heat_Min > FWM_Auto_Add_Heat_Max*

0x18 — EWMSmartT124h

Value	Temperature [C]	Description
150	15,0	Minimum value
240	24,0*	Maximum value

Default value: 17,0 (170)

(*) $EWM\_Smart\_T1\_24h\_ref <= EWM\_Smart\_T1\_3h\_ref - 1$ [K]

0x19 — EWMSmartT13h

Value	Temperature [C]	Description
160	16,0*	Minimum value
250	25,0	Maximum value

Default value: 21,0 (210)

(*) $EWM\_Smart\_T1\_3h\_ref >= EWM\_Smart\_T1\_24h\_ref + 1$ [K]

0x1A — HeatT3_PI_KP

Value [%]	Description
0	Minimum value
100	Maximum value

Default value: 3

0x1B — HeatT3_PI_TI

Value [%]	Description
0	Minimum value
600	Maximum value

Default value: 3*60 = 180 [s]

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📞 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

82

Address	Name	Description
0x1C	HeatT5_PI_KP	KP gain value of the PI controller for the return water temperature control system (T5).
		Value [%] / **Description** table follows
0x1D	HeatT5_PI_TI	The value of the TI time of the PI controller for the return water temperature control system (T5).

0x1C — HeatT5_PI_KP

Value [%]	Description
0	Minimum value
100	Maximum value

Default value: 3

0x1D — HeatT5_PI_TI

Value [%]	Description
0	Minimum value
600	Maximum value

Default value: 3*60 = 180 [s]

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   ☐ 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

83

2.14. DRV LUNA(LUNA – Fan Heater)

2.14.1. INPUT REGISTER DRV LUNA

Address	Name	Description		
0x01	Software_type			
		Parameter	**Description**	**Value**
		LUNA	LUNA Hard	2306
0x02	Software_Type			
		Parameter	**Description**	**Value**
		LUNA	LUNA Soft	5890
0x03	Connection count	Register for internal use.		
0x04	Soft_ver	Register for internal use.		
0x05	RoomTempeartureValue	Temperature measured by T4 sensor (room temperature).		
		Value	**Temperature [C]**	**Description**
		–150	–15,0	Minimal value
		950	95,0	Maximal value
0x06	LeadTempeartureValue	Temperature measured by Leading sensor (MODBUS, ROOM, SUPLY, INTAKE).		
		Value	**Temperature [C]**	**Description**
		–150	–15,0	Minimal value
		950	95,0	Maximal value
0x07	IntakeTempeartureValue	Temperature measured by Ti3 sensor (inlet air).		
		Value	**Temperature [C]**	**Description**
		–150	–15,0	Minimal value
		950	95,0	Maximal value
0x08	SuplyTempeartureValue	Temperature measured by T1 sensor (outlet air).		
		Value	**Temperature [C]**	**Description**
		–150	–15,0	Minimal value
		950	95,0	Maximal value
0x09	HeaterTempeartureValue	Temperature measured by T2 sensor (water exchanger).		
		Value	**Temperature [C]**	**Description**
		–150	–15,0	Minimal value
		950	95,0	Maximal value
0x0A	FanEffciencyValue	Fan Efficeincy.		
		Value	**Efficeincy [%]**	**Description**
		0	0	Minimum value
		1000	100	Maximum value

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

84

Address	Name	Description
0x0B	DrainPumpAlarm	Drain pump alarm state. | Value	Description	Alarm
---	---	---
0	Alarm off	
1	Alarm active	**ALARM**	
0x0C	FilterWorkTime	Filter work time. | Value	Filter work time [min]	Description
---	---	---
0	0	Minimum value
32767	5*32767	Maximum value | Example: If the value of the IR register [0x0C]=12, the operating time is 5x12=60 min
0x0D	ValveHTValue	Current state of the heating valve. | Value	Opening status [%]	Description
---	---	---
0	0	Valve close
1000	100	Valve open to maximum	
0x0E	ValveCLValue	Current state of the cooling valve: | Value	Opening status [%]	Description
---	---	---
0	0	Valve close
1000	100	Valve open to maximum	
0x0F	Smart1State	Information whether the mode is active. 	Value	Description
---	---
0	OFF
1	Active	
0x10	Smart2State	Information whether the mode is active. 	Value	Description
---	---
0	OFF
1	Active	
0x11	Smart3State	Information whether the mode is active. 	Value	Description
---	---
0	OFF
1	Active	
0x12	TechnologicalHeatAlarm	Lack of the heat from the source. | Value	Description	Alarm
---	---	---
0	Alarm off	
1	Alarm active	**ALARM**	
0x13	Smart2LowTempAlarm	Low supply temperature – II state. 	Value	Description
---	---
0	Alarm off
1	Alarm active	

Address	Name	Description			
0x14	SuplyTempeartureValue	Temperature measured by T1 sensor (outlet air).			
		Value	**Temperature [C]**	**Description**	**Alarm**
		–150	–15,0	Minimal value	
		950	95,0	Maximal value	
		1100	–	Short circuit	
		–250	–	NTC sensor not connected	**ALARM**
0x15	HeaterTempeartureValue	Temperature measured by T2 sensor (water exchanger).			
		Value	**Temperature [C]**	**Description**	**Alarm**
		–150	–15,0	Minimal value	
		950	95,0	Maximal value	
		1100	–	Short circuit	
		–250	–	NTC sensor not connected	**ALARM**
0x16	IntakeTempeartureValue	Temperature measured by T3 sensor (inlet air).			
		Value	**Temperature [C]**	**Description**	**Alarm**
		–150	–15,0	Minimal value	
		950	95,0	Maximal value	
		1100	–	Short circuit	
		–250	–	NTC sensor not connected	**ALARM**
0x17	RoomTempeartureValue	Temperature measured by T4 sensor (room air).			
		Value	**Temperature [C]**	**Description**	**Alarm**
		–150	–15,0	Minimal value	
		950	95,0	Maximal value	
		1100	–	Short circuit	
		–250	–	NTC sensor not connected	**ALARM**
0x18	InputDIState	State of Di-connector.			
		Value		**Description**	
		0		OFF	
		1		Active	
0x19	FanWorkTime	Fan work time.			
		Value	**Filter work time [h]**	**Description**	
		0	0	Minimum value	
		32767	32767	Maximum value	
0x1A	PreheatState	Preheat state.			
		Value		**Description**	
		0		OFF	
		1		Maximum value of temperature	

2.14.2. HOLDING REGISTER DRV LUNA

Address	Name	Description
0x01	OnOff	Work mode. | Value	Work status	Description | |---|---|---| | 0x00 | OFF | Device Off | | 0x01 | ON | Device On | **Default: OFF (0x00)**
0x02	ManualWorkMode	Fan mode. | Value	Name	Description | |---|---|---| | 0x01 | MANUAL | Fan work in manual mode | | 0x02 | AUTO | Fan work in auto mode. | **Default: MANUAL (0x01)**
0x03	DestratificatioinMode	Enable/disable Destratification mode. | Value	Work status	Description | |---|---|---| | 0x00 | OFF | disable | | 0x01 | ON | enable | **Default: OFF (0x00)** Function active if Low Ceiling Mode HR *[0x04]*==OFF
0x04	LowCeilingMode	Enable/disable Low Ceiling mode: | Value	Work status	Description | |---|---|---| | 0x00 | OFF | disable | | 0x01 | ON | enable | **Default: OFF (0x00)**
0x05	NozzleLvl	Nozzle Settings (Parameter adjustable in 5 steps). | Val [%]	Description | |---|---| | 0 | Nozzle closed (air flow directed vertically down) | | 25 | Nozzle 25% open | | 50 | Nozzle 50% open | | 75 | Nozzle 75% open | | 100 | Nozzle 100% open (air flow directed sideways "horizontally") | **Defaut: 0%** Function active if Manual Work Mode HR *[0x02]*==ON
0x06	SmartMode	Enable/disable Smart Mode. | Value	Work status	Description | |---|---|---| | 0x00 | OFF | disable | | 0x01 | ON | enable | **Default: 0x00** Function active if Input DI Configuration *[0x16]*==1 or 2

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

87

Address	Name	Description
0x07	PreheatMode	Enable/disable preheat.

Value	Work status	Description
0x00	OFF	disable
0x01	ON	enable

Default: 0x00

Function active if Exchanger Type Configuration HR *[0x18]*==0 or 2

Address	Name	Description
0x08	FanManualLvl	Manual Fan Efficiency:

Value	Efficience [%]	Description
200	20	Min. fan speed allowed in manual mode
1000	100	Max. fan speed allowed in manual mode

Default: 20% (200)

Function active if Register *[0x02]* ==1

Address	Name	Description
0x09	DestratificationTempRef	Temperature difference value defining the activation of the function.

Value	Temperature [°C]	Description
20	2,0	Minimum value
60	6,0	Maximum value

Default: 5,0°C (50)

IntakeTempeartureValue IR *[0x07]* - RoomTempeartureValue IR *[0x05]* >

DestartificationTempRef HR *[0x09]*

Address	Name	Description
0x0A	PreheatTempRef	The exchanger temperature value *[IR0x09]* after which the fan is turn on (applies to Heating Mode).

Value	Temperature [°C]	Description
280	28,0	Minimum value
370	37,0	Maximum value

Default: 28,0°C (280)

Address	Name	Description
0x0B	SmartMode1TimeRef	The time value after which the SMART MODE I condition will be activated.

Value	Time [s]	Description
0	0	Minimum value
7200	7200	Maximum value

Default 1800 s (1800)

Address	Name	Description
0x0C	SmartMode2TimeRef	The time value after which the SMART MODE II condition will be activated.

Value	Time [s]	Description
0	0	Minimum value
14400	14400	Maximum value

Default 3600 s (3600)

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📞 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

88

Address	Name	Description
0x0D	SmartMode3TimeRef	The time value after which the SMART MODE II condition will be activated.

Value	Time [s]	Description
0	0	Minimum value
28800	28800	Maximum value

Default 7200 s (7200)

Address	Name	Description
0x0E	SmartMode2HysteresisHeat	Temperature hysteresis for heating.

Value	Temperature [°C]	Description
10	1,0	Minimum value
50	5,0	Maximum value

Default: 2°C (20)

Address	Name	Description
0x0F	SmartMode2HysteresisCool	Temperature hysteresis for cooling.

Value	Temperature [°C]	Description
10	1,0	Minimum value
50	5,0	Maximum value

Default: 2°C (20)

Address	Name	Description
0x10	SmartMode3TempMin	Minimum temperature for SMART MODE III.

Value	Temperature [°C]	Description
160	16,0	Minimum value
210	21,0	Maximum value

Default:18°C (180)

Address	Name	Description
0x11	InputDiForce	Parameter overwritten by MODBUS when the parameter InputDIConfiguration HR [0x16] is activated for minimum 1 Device. Value read from IR [0x1E]

Value	Description
0	disable
1	enable

Default:0

Activation: InputDIForce HR [0x11]==1

The condition must be met: InputDIConfiguration HR [0x16]= 1 or 2 and: IR [0x0E]==1

Address	Name	Description
0x12	DestratificationFanRef	Fan efficiency in Destratification mode.

Value	Fan Speed [%]	Description
400	40	Minimum value
1000	100	Maximum value

Default: 60% (600)

FLOWAIR Sp. z o.o.

ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

89

Address	Name	Description
0x13	LowCeilingFanRef	Fan efficiency in Low ceiling mode.

Value	Fan Speed [%]	Description
0	0	Minimum value
1000	100	Maximum value

Default: 60% (600)

The minimum value is limited by changing the value in the HR register *[0x14]*.

The maximum value is limited by changing the value in the HR register *[0x15]*.

Address	Name	Description
0x14	LowCeilingLowLimit	The low limit for fan efficiency in Low Ceiling mode.

Value	Fan Speed [%]	Description
0	0	Minimum value
1000	100	Maximum value

Default: 0% (0)

Address	Name	Description
0x15	LowCeilingHighLimit	The high limit or fan efficiency in Low Ceiling mode.

Value	Fan Speed [%]	Description
0	0	Minimum value
1000	100	Maximum value

Default: 60% (600)

Address	Name	Description
0x16	InputDIConfiguration	Activation and selection of contact polarization.

Value	Type	Description
0	OFF	Contact inactive
1	NC	Contact Normally Closed
2	NO	Contact Normally Open

Address	Name	Description
0x17	ActuatorsTime Configuration	The parameter value responsible for the correct operation of the 3P actuator. The parameter value should be consistent with the opening time value provided by the actuator manufacturer.

Value	Time [s]	Description
0	0	Minimum value
2000	2000	Maximum value

Default: 150s (150)

Address	Name	Description
0x18	ExchangerType Configuration	Type of exchanger.

Value	Description
0	Heat exchanger for Heating
1	Heat echanger for Cooling
2	Heat exchanger for Heating/cooling

Default: 2

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   58 627 57 20   info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

90

Address	Name	Description
0x19	ValveTypeConfiguration	Type of valve actuator.

Value	Description
0	3-point actuator
1	ON/OFF actuator

Default: 0

Address	Name	Description
0x1A	DrainPumpAlarm Configuration	Selecting the polarity of the condensate pump alarm contact.

Value	Description
0	Alarm contact deactivated
1	NC polarity
2	NO polarity

Default: 0

Address	Name	Description
0x1B	FilterMaxWorkTime	Setting the maximum filter operating time.

Value	Time [h]	Description
0	0	Minimum value
4000	4000	Maximum value

Default: 4000h (4000)

Address	Name	Description
0x1C	GroupTLeadSensorSelect	Selection of the lead sensor

Val	Description
1	Leading temperature value sent via MODBUS
2	Value from the Ti1 SUPPLY sensor
3	Value from the Ti4 ROOM sensor
4	Value from the Ti3 INTAKE sensor

FLOWAIR Sp. z o.o.
ul. Chwaszczyńska 135, 81-571 Gdynia   NIP: 9581440661   📱 58 627 57 20   ✉ info@flowair.pl   **www.flowair.com**

T-BOX Zone Modbus RTU V4.7.docx

91